R-Tanks (Elevation-Volume-Flow Table (Pond), 25 years (Post-Development 25 Year))...44

R-Tanks (OUT) (Pond Routed Hydrograph (total out), 25 years (Post-Development 25 Year))...45, 46

Т

Time-Depth - 1 (Time-Depth Curve, 25 years (Post-Development 25 Year))...2, 3

Time-Depth - 1 (Time-Depth Curve, 25 years (Pre-Development 25 Year))...4, 5

EDA-PDA.ppc 8/25/2020 Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 48 of 48

APPENDIX B

NYSDEC STORMWATER SIZING CALCULATIONS

CISTERN WORKSHEET		JMC Project:	18100
		Design Point:	DL-1
RAINWATER HARVESTING TANK CALCULATIO	ONS	Drainage Area: Pl	DA-1A
Site Data for Drainage Area to be Treated by Practice			
DESCRIPTION	SYMBOL	VALUE	UNITS
Design Storm [90% Rainfall Event Number]	Р	1.5	In
Impervious Area	Ι	0.14	Ac
Area	А	0.31	Ac
Percent Impervious	%I	45.20	%
Runoff Coefficient [0.05 + 0.009 x %I]	R _v	0.46	CF
TOTAL VOLUME Required $[WQ_V = (P \times R_V \times A) / 12]$	WQ _V	760	CF
Minimum Cistern Size			
DESCRIPTION	SYMBOL	VALUE	UNITS
Water Quality Volume	WQv	760	CF
Conversion Factor (7.5 gals/cf)		7.50	Gals/CF
Required Cistern Volume Vol = (WQ _V x 7.5)	Vol	5,703	Gals
Proposed Cistern Size			
DESCRIPTION	SYMBOL	VALUE	UNITS
Provided Cistern Model	-	Woodards Concrete ST-3000	-
Provided Cistern Volume (Per Cistern)	-	3,000	Gal
Provided Cistern Volume (Length x Width x Height)	PVol	6,000	Gal

APPENDIX C

TEMPORARY EROSION AND SEDIMENT CONTROL & PERMANENT STORMWATER PRACTICE INSPECTION CHECKLIST

JMC Project 18100 Residential Development 1165 Greacen Point Road Village of Mamaroneck, NY

Temporary Erosion and Sediment Control Inspection and Maintenance Checklist

Erosion and Sediment Control Measure	Inspection/Maintenance Intervals	Inspection/Maintenance Requirements
Stabilized Construction Entrance	Daily	 Periodic top dressing with additional aggregate as required Clean sediment in public right-of- ways immediately
Silt Fence	Weekly + After Each Rain	 Remove & redistribute sediment when bulges develop in the silt fence.
Inlet Protection	Weekly + After Each Rain	 Remove sediment as necessary and replace filter fabric, crushed stone etc. Any broken and damaged components should be replaced. Check all materials for proper anchorage and secure as necessary.

JMC Project 18100 Residential Development 1165 Greacen Point Road Village of Mamaroneck, NY

Permanent Stormwater Management Practice Inspection and Maintenance Checklist

Stormwater Management	Inspection/Maintenance Intervals	Inspection/Maintenance Requirements
Practice		
Rip-Rap Apron/Energy Dissipator and Check Dams	Annually + After Major Storms	 Check for evidence of flows going around the structure. Check for evidence at downstream toe and repair as needed. Clean sediment and install additional aggregate as necessary.
Drain Inlets	Monthly	 Check for blockage and/or erosion at top of each inlet. Repair/remove as necessary. Check for sediment and debris collected within sumps and clean out as necessary.
Subsurface Stormwater Management Detention Facility	Annually + After Major Storms	 Check level of sediment and debris accumulated within the system. Check structural integrity of the system pipes, structures, etc. for cracking, bulging or deterioration. Repair/remove as necessary. Confirm all inlets and outlet structures/pipes are operating properly.

The owner/operator responsible for inspection and maintenance as outlined above:

Mr. William Fedyna 219 W 81st Street, Apt. 9D New York, NY 10024 Phone: (646) 321-2081

p:\2018\18100\drainage\reports\2020-06-02_pd (swppp)\appendices\temporary & permanent s&e inspection and maintenance checklist.docx

APPENDIX D

CONTRACTOR'S CERTIFICATION



Site Planning Civil Engineering Landscape Architecture Land Surveying Transportation Engineering Environmental Studies Entitlements Construction Services 3D Visualization Laser Scanning

JMC Project 18100 Residential Development 1165 Greacen Point Road Village of Mamaroneck, NY

CONTRACTOR'S CERTIFICATION

"I hereby certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the owner or operator must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I am aware that there are significant penalties for submitting false information, that I do not believe to be true, including the possibility of fine and imprisonment for knowing violations"

Company Name:	
Address:	
Telephone Number:	
Name and Title:	
Signature:	_Date:
Permit Identification No.:	
Name and Title of Trained Contractor:	
Elements of the SVA/PPP Contractor is responsible for:	

p:\2018\18100\drainage\reports\2020-06-02_pd (swppp)\appendices\nys contractors certification.docx

JMC Planning Engineering Landscape Architecture & Land Surveying, PLLC | JMC Site Development Consultants, LLC

APPENDIX E

STONE OUTLET PROTECTION DESIGN CALCULATIONS



Figure 3.16

New York State Standards and Specifications For Erosion and Sediment Control

La MIMUMUM LENGTH OF APRON: 6'

d50 RIP RAP SIZE: 3"

APPENDIX F

R-TANK DETAILS AND SPECIFICATIONS







	DOUBLE	
	204	
	1,700 CF	
	1,035 SF	
	68 CY	
	2,118 SF (235 SY)	
ON	4,236 SF (471 SY)	
	1680 SF (187 SY)	
	1	
	2	
R AND 3" OI	F BASE.	
E A 15% W	ASTE FACTOR.	









R-TANK SPECIFICATION

PART 1 - GENERAL

- 1.01 Related Documents
- Drawings, technical specification and general provisions of the Contract as modified herein apply to this section.

1.02 Description of Work Included

- Provide excavation and base preparation per geotechnical engineer's recommendations and/or as shown on the design drawings, to provide adequate support for project design loads and safety from excavation sidewall collapse. Excavations shall be in accordance with the owner's and OSHA requirements
- в Provide and install R-Tank^{LD}, R-Tank^{LD}, R-Tank^{SD}, or R-TANK outlet pipe with connections per the manufacturer's installation guidelines provided in this section.
- Provide and construct the cover of the R-Tank system including; stone backfill, structural fill cover, and pavement section as specified.
- Protect R-Tank system from construction traffic after installation until completion of all construction activity in the installation area.

1.03 Quality Control

- All materials shall be manufactured in ISO certified facilities. Α.
- Installation Contractor shall demonstrate the following experience: . A minimum of three R-Tank or equivalent projects completed within 2 years; and,
- 2. A minimum of 25,000 cubic feet of storage volume completed within 2 years.
- 3. Contractor experience requirement may be waived if the manufacturer's representative provides on-site training and review during construction.
- Installation Personnel: Performed only by skilled workers with satisfactory record of performance on bulk earthworks, pipe, chamber, or pond/landfill construction projects of comparable size and quality
- D. Contractor must have manufacturer's representative available for site review if requested by Owner

1.04 Submittals

C.

- Α. Submit proposed R-Tank layout drawings. Drawings shall include typical section details as well as the required base elevation of stone and tanks, minimum cover requirements and tank configuration.
- Submit manufacturer's product data, including compressive strength and unit weight.
- Submit manufacturer's installation instructions.
- Submit R-Tank sample for review. Reviewed and accepted samples will be returned to the Contractor.
- Submit material certificates for geotextile, geogrid, base course and backfill materials. Submit required experience and personnel requirements as specified in Section 1.03.
- Any proposed equal alternative product substitution to this specification must be submitted for review and approved prior to bid opening. Review package should include third party reviewed performance data that meets or exceeds criteria in Table 2.01 B.
- 1.05 Delivery, Storage, and Handling
- Protect R-Tank and other materials from damage during delivery, and store UV sensitive materials under tarp to protect from sunlight when time from delivery to installation Α. exceeds two weeks. Storage of materials should be on smooth surfaces, free from dirt, mud and debris.
- Handling is to be performed with equipment appropriate to the materials and site conditions, and may include hand, handcart, forklifts, extension lifts, etc. Cold weather:
- Care must be taken when handling plastics when air temperature is 40 degrees or below as plastic becomes brittle.
- 2. Do not use frozen materials or materials mixed or coated with ice or frost.
- 3. Do not build on frozen ground or wet, saturated or muddy subgrade.

1.06 Preinstallation Conference.

Prior to the start of the installation, a preinstallation conference shall occur with the representatives from the design team, the general contractor, the excavation contractor, the R-Tank installation contractor, and the manufacturer's representative

1.07 Project Conditions

- Coordinate installation for the R-Tank system with other on-site activities to eliminate all non-installation related construction traffic over the completed R-Tank system. No loads heavier than the design loads shall be allowed over the system, and in no case shall loads higher than a standard AASHTO HS20 (or HS25, depending on design criteria) load be allowed on the system at any time.
- Protect adjacent work from damage during R-Tank system installation.
- All pre-treatment systems to remove debris and heavy sediments must be in place and functional prior to operation of the R-Tank system. Additional pretreatment measures may be needed if unit is operational during construction due to increased sediment loads.
- D. Contractor is responsible for any damage to the system during construction.

PART 2 - PRODUCTS

- 2 01 R-Tank Units
- R -Tank Injection molded plastic tank plates assembled to form a 95% void modular structure of predesigned height (custom for each project).
- R-Tank units shall meet the following Physical & Chemical Characteristics:

PROPERTY	DESCRIPTION	R-Tank ^{LD} VALUE	R-Tank ^{HD} VALUE	R-Tank ^{SD} VALUE	R-Tank ^{UD} VALUE
Void Area	Volume available for water storage	95%	95%	95%	95%
Surface Void Area	Percentage of exterior available for infiltration	90%	90%	90%	90%
Compressive Strength	ASTM D 2412 / ASTM F 2418	30.0 psi	33.4 psi	42.9 psi	134.2 psi
HS-20 Minimum Cover	Cover required to support HS-20 loads	N/A	20"	18"	12" (STONE BACKFILL)
HS-25 Minimum Cover	Cover required to support HS-25 loads	N/A	24"	19"	15" (STONE BACKFILL)
Maximum Cover	Maximum allowable cover depth	3 feet	< 7 feet	< 10 feet	5 feet
Unit Weight	Weight of plastic per cubic foot of tank	3.29 lbs / cf	3.62 lbs/cf	3.96 lbs / cf	4.33 lbs / cf
Rib Thickness	Thickness of load-bearing members	0.18 inches	0.18 inches	0.18 inches	N/A
Service Temperature	Safe temperature range for use	-14 - 167° F	-14 - 167° E	-14 - 167° E	-14 - 167° E

- Supplier: ACF Environmental 2831 Cardwell Road Richmond, VA 23234 C.
- (T): 800-448-3636; (F): 804-743-7779 www.acfenvironmental.com

2.02 Geosynthetics

- Geotextile. A geotextile envelope is required to prevent backfill material from entering the R-Tank modules.
- 1. Standard Application: The standard geotextile shall be an 8 oz per square yard nonwoven geotextile (ACF N080 or equivalent). 2. Infiltration Applications: When water must infiltrate/exfiltrate through the geotextile as a function of the system design, a woven monofilament (ACF M200 or equivalent) shall be
- Geogrid. For installations subject to traffic loads and/or when required by project plans, install geogrid (ACF BX12 or equivalent) to reinforce backfill above the R-Tank system. Β.
- Geogrid is not always required for R-Tank^{UD} installations, and is often not required for non-traffic load applications

2.03 Backfill & Cover Materials

- Bedding Materials: Stone (angular and smaller than 1.5" in diameter) or soil (GW, GP, SW, or SP as classified by the Unified Soil Classification System) shall be used below the R-Tank system (3" minimum). Material must be free from lumps, debris, and any sharp objects that could cut the geotextile. Material shall be within 3 percent of the optimum moisture content as determined by ASTM D698 at the time of installation. For infiltration applications bedding material shall be free draining.
- Side and Top Backfill: Free draining material shall be used adjacent to (24" minimum) and above (for the first 12") the R-Tank system. Material must be free from lumps, debris в and any sharp objects that could cut the geotextile. Material shall be within 3 percent of the optimum moisture content as determined by ASTM D698 at the time of installation. 1. For LD, HD, and SD modules, backfill materials shall be free draining stone (angular and smaller than 1.5" in diameter) or soil (GW, GP, SW, or SP as classified by the Unified Soil Classification System).
- 2. For UD modules in traffic loaded (HS-20) applications with less than 14" of top cover, side backfill materials shall be free draining stone (angular and smaller than 1.5" in diameter). The use of soil backfill on the sides of the UD module is not permitted unless the modules are installed outside of traffic areas or with cover depths of > 14". Top backfill material may be stone or soil as noted above (Section 2.03 B 1).
- Additional Cover Materials: Structural Fill shall consist of granular materials meeting the gradational requirements of SM, SP, SW, GM, GP or GW as classified by the Unified Soil Classification System. Structural fill shall have a maximum of 25 percent passing the No. 200 sieve, shall have a maximum clay content of 10 percent and a maximum Plasticity index of 4. Material shall be within 3 percent of the optimum moisture content as determined by ASTM D698 at the time of installation

2.04 Other Materials

Utility Marker: Install metallic tape at corners of R-Tank system to mark the area for future utility detection.

PART 3 - EXECUTION

- 3.01 Assembly of R-Tank Units
- Assembly of modules shall be performed in accordance with the R-Tank Installation Manual. Section 2.

3.02 Lavout and Excavation

- Installer shall stake out, excavate, and prepare the subgrade area to the required plan grades and dimensions, ensuring that the excavation is at least 2 feet greater than R-Tank dimensions in each direction allowing for installation of geotextile filter fabric, R-Tank modules, and free draining backfill materials
- All excavations must be prepared with OSHA approved excavated sides and sufficient working space. C. Protect partially completed installation against damage from other construction traffic by establishing a perimeter with high visibility construction tape, fencing, barricades, or other means until construction is complete.
- D Base of the excavation shall be uniform, level, and free of lumps or debris and soft or yielding subgrade areas. A minimum 2,000 pounds per square foot bearing capacity is required.
- Standard Applications: Compact subgrade to a minimum of 95% of Standard Proctor (ASTM D698) density or as required by the Owner's engineer
- 2. Infiltration Applications: Subgrade shall be prepared in accordance with the contract documents. Compaction of subgrade should not be performed in infiltration applications. Unsuitable Soils or Conditions: All questions about the base of the excavation shall be directed to the owner's engineer, who will approve the subgrade conditions prior to Ε.
- placement of stone. The owner's engineer shall determine the required bearing capacity of the R-Tank subgrade; however in no case shall a bearing capacity of less than 2,000 pounds per square foot be provided
- 1. If unsuitable soils are encountered at the subgrade, or if the subgrade is pumping or appears excessively soft, repair the area in accordance with contract documents and/or as directed by the owner's engineer.
- 2. If indications of the water table are observed during excavation, the engineer shall be contacted to provide recommendations.
- 3. Do not start installation of the R-Tank system until unsatisfactory subgrade conditions are corrected and the subgrade conditions are accepted by the owner's engineer.

3.03 Preparation of Base

- Place a thin layer (3" unless otherwise specified) of bedding material (Section 2.03 A), over the subgrade to establish a level working platform for the R-Tank modules. Level to within 1/2" (+/- 1/2") or as shown on the plans. Native subgrade soils or other materials may be used if determined to meet the requirements of 2.03 A and are accepted by the owner's engineer
- Standard Applications: Static roll or otherwise compact bedding materials until they are firm and unyielding.
- . Infiltration Applications: Bedding materials shall be prepared in accordance with the contract documents в Outline the footprint of the R-Tank system on the excavation floor using spray paint or chalk line to ensure a 2' perimeter is available around the R-Tank system for proper installation and compaction of backfill

3.04 Installation of the R-Tanks

- Where a geotextile wrap is specified on the stone base, cut strips to length and install in excavation, removing wrinkles so material lavs flat. Overlap geotextile a minimum 12" or as recommended by manufacturer.
- В. Where an impervious liner (for containment) is specified, install the liner per manufacturer's recommendations and the contract documents. The R-Tank units shall be separated from impervious liner by a non-woven geotextile fabric installed accordance with Section 3.04A.
- C. Install R-Tank modules by placing side by side, in accordance with the design drawings. No lateral connections are required. It is advisable to use a string line to form square corners and straight edges along the perimeter of the R-Tank system. The modules are to be oriented as per the design drawing with required depth as shown on plans. For LD, HD, and SD installations, the large side plate of the tank should be placed on the perimeter of the system. This will typically require that the two ends of the tank area will have a row of tanks placed perpendicular to all other tanks. If this is not shown in the construction drawings, it is a simple field adjustment that will have minimal effect on the
- overall system footprint. Refer to R-Tank Installation Guide for more details
- 2. For UD installations, there is no perpendicular end row required.
- Wrap the R-Tank top and sides in specified geotextile. Cut strips of geotextile so that it will cover the sides and top, encapsulating the entire system to prevent backfill entry into D. the system. Overlap geotextile 12" or as recommended by manufacturer. Take great care to avoid damage to geotextile (and, if specified, impervious liner) during placement. F Identify locations of inlet, outlet and any other penetrations of the geotextile (and optional liner). These connections should be installed flush (butted up to the R-Tank) and the geotextile fabric shall be cut to enable hydraulic continuity between the connections and the R-Tank units. These connections shall be secured using pipe boots with stainless
- steel pipe clamps. Support pipe in trenches during backfill operations to prevent pipe from settling and damaging the geotextile, impervious liner (if specified) or pipe. Connecting pipes at 90 degree angles facilitates construction, unless otherwise specified. Ensure end of pipe is installed snug against R-Tank system. Install Inspection and Maintenance Ports in locations noted on plans. At a minimum one maintenance port shall be installed within 10' of each inlet & outlet connection, and with a
- maximum spacing of one maintenance port for every 2,500 square feet. Install all ports as noted in the R-Tank Installation Guide. G. If required, install ventilation pipes and vents as specified on drawings to provide ventilation for proper hydraulic performance. The number of pipes and vents will depend on the
- size of the system. Vents are often installed using a 90 degree elbow with PVC pipe into a landscaped area with 'U" bend or venting bollard to inhibit the ingress of debris. A ground level concrete or steel cover can be used

3.05 Backfilling of the R-Tank Units

- Backfill and fill with recommended materials as follows:
- Place freely draining backfill materials (Section 2.03 B) around the perimeter in lifts with a maximum thickness of 12". Each lift shall be placed around the entire perimeter such that each lift is no more than 24" higher than the side backfill along any other location on the perimeter of the R-Tank system. No fill shall be placed over top of tanks until the side backfill has been completed.
- 2. Each lift shall be compacted at the specified moisture content to a minimum of 95% of the Standard Proctor Density until no further densification is observed (for self-compacting stone materials). The side lifts must be compacted with walk behind compaction equipment. Even when "self-compacting" backfill materials are selected, a walk behind vibratory compactor must be used.
- 3. Take care to ensure that the compaction process does not allow the machinery to come into contact with the modules due to the potential for damage to the geotextile and R-Tank units.
- 4. No compaction equipment is permissible to operate directly on the R-Tank modules.
- 5. Top Backfill:
 - a. Typical Applications: Install a 12" (or as shown on plans) lift of freely draining material (Section 2.03 B) over the R-Tank Units, maintaining 12" between equipment tracks and R-Tank System
 - b. Shallow Applications (< 18" total cover): Install top backfill in accordance with plans.

Lightly compacted using a walk-behind trench roller. Alternately, a roller (maximum gross vehicle weight of 6 tons) may be used. Roller must remain in static mode until a minimum of 24" of cover has been placed over the modules. Sheep foot rollers should not be used.

- 6. If required, install a geogrid as shown on plans. Geogrid shall extend a minimum of 3 feet beyond the limits of the excavation wall. Following placement and compaction of the initial cover, subsequent lifts of structural fill (Section 2.03 C) shall be placed at the specified moisture content and compacted to a minimum of 95% of the Standard Proctor Density and shall cover the entire footprint of the R-Tank system. During placement of fill above the system, unless otherwise specified,
- a uniform elevation of fill shall be maintained to within 12" across the footprint of the R-Tank system. Do not exceed maximum cover depths listed in Table 2.01 B. 8. Place additional layers of geotextile and/or geogrid at elevations as specified in the design details. Each layer of geosynthetic reinforcement placed above the R-Tank system
- shall extend a minimum of 3 feet beyond the limits of the excavation wall. Only low pressure tire or track vehicles shall be operated over the R-Tank system during construction. No machinery should drive on top of the tank until a minimum of 18" of
- backfill and compaction is achieved. Dump Trucks and Pans shall not be operated within the R-Tank system footprint at any time. Where necessary the heavy equipment should unload in an area adjacent to the R-Tank system and the material should be moved over the system with tracked equipmen C.
- related loading should be allowed over the R-Tank system until the final design section has been constructed (including pavement)
- D. Place surfacing materials, such as groundcovers (no large trees), or paving materials over the structure with care to avoid displacement of cover fill and damage to surrounding
- F Backfill depth over R-Tank system must be within the limitations shown in the table in Section 2.01 B. If the total backfill depth does not comply with this table, contact engineer or manufacturer's representative for assistance.

PART 4 - USING THE SYSTEM 4 01 Maintenance Requirements

C.

manufacturer's guidelines (for proprietary systems).

through the loose sediments, allowing a depth measurem

through a Dirtbag or approved equivalent if permitted by the locality.

Ensure that all unrelated construction traffic is kept away from the limits of excavation until the project is complete and final surface materials are in place. No non-installation

A routine maintenance effort is required to ensure proper performance of the R-Tank system. The Maintenance program should be focused on pretreatment systems. Ensuring these structures are clean and functioning properly will reduce the risk of contamination of the R-Tank system and stormwater released from the site. Pre-treatment systems shall be inspected yearly, or as directed by the regulatory agency and by the manufacturer (for proprietary systems). Maintain as needed using acceptable practices or following

Inspection and/or Maintenance Ports in the R-Tank system will need to be inspected for accumulation of sediments at least guarterly through the first year of operation and at least yearly thereafter. This is done by removing the cap of the port and using a measuring device long enough to reach the bottom of the R-Tank system and stiff enough to push

If sediment has accumulated to the level noted in the R-Tank Maintenance Guide or beyond a level acceptable to the Owner's engineer, the R-Tank system should be flushed. A flushing event consists of pumping water into the Maintenance Port and/or adjacent structure, allowing the turbulent flows through the R-Tank system to re-suspend the fine sediments. If multiple Maintenance Ports have been installed, water should be pumped into each port to maximize flushing efficiency. Sediment-laden water can be filtered



APPENDIX G

DRAWINGS

SITE PLAN APPROVAL DRAWINGS **RESIDENTIAL DEVELOPMENT** TAX MAP SECTION 9 | BLOCK 50 | LOT 373 WESTCHESTER COUNTY **1165 GREACEN POINT ROAD** MAMARONECK, NY, 10543

Applicant/Owner: MR. WILLIAM FEDYNA & ELISABETH FEDYNA 219 W 81ST STREET, APT. 9D **NEW YORK, NY, 10024**

Architect:

ARCHI-TECTONICS 111 JOHN ST #700 NEW YORK, NY 10038 (212)206-0920

Attorney:

CUDDY & FEDER LLP 445 HAMILTON AVENUE, 14TH FLOOR WHITE PLAINS, NY 10601 (914)761-1300

Surveyor:

SPINELLI SURVEYING 650 HALSTEAD AVENUE MAMARONECK, NY 10543 (914) 381-2357



Site Planner, Civil & Traffic Engineer, **Surveyor and Landscape Architect:** 120 BEDFORD ROAD **ARMONK, NY 10504** (914) 273-5225



LE	GEND
	SITE PROPERTY LINE
	ZONING BOUNDARY
MR	MARINE RECREATION
R-20	RESIDENTIAL ZONE



GENERAL CONSTRUCTION NOTES APPLY TO ALL WORK HEREIN:

1. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CALL 811 "DIG SAFELY" (1-800-962-7962) TO HAVE UNDERGROUND UTILITIES LOCATED. EXPLORATORY EXCAVATIONS SHALL COMPLY WITH CODE 753 REQUIREMENTS. NO WORK SHALL COMMENCE UNTIL ALL THE OPERATORS HAVE NOTIFIED THE CONTRACTOR THAT THEIR UTILITIES HAVE BEEN LOCATED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PRESERVATION OF ALL PUBLIC AND PRIVATE UNDERGROUND AND SURFACE UTILITIES AND STRUCTURES AT OR ADJACENT TO THE SITE OF CONSTRUCTION, INSOFAR AS THEY MAY BE ENDANGERED BY THE CONTRACTOR'S OPERATIONS. THIS SHALL HOLD TRUE WHETHER OR NOT THEY ARE SHOWN ON THE CONTRACT DRAWINGS. IF THEY ARE SHOWN ON THE DRAWINGS, THEIR LOCATIONS ARE NOT GUARANTEED EVEN THOUGH THE INFORMATION WAS OBTAINED FROM THE BEST AVAILABLE SOURCES, AND IN ANY EVENT, OTHER UTILITIES ON THESE PLANS MAY BE ENCOUNTERED IN THE FIELD. THI CONTRACTOR SHALL, AT HIS OWN EXPENSE, IMMEDIATELY REPAIR OR REPLACE ANY STRUCTURES OR UTILITIES THAT HE DAMAGES, AND SHALL CONSTANTLY PROCEED WITH CAUTION TO PREVENT UNDUE INTERRUPTION OF UTILITY SERVICE.

- 2. CONTRACTOR SHALL HAND DIG TEST PITS TO VERIFY THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR SHALL VERIFY EXISTING UTILITIES DEPTHS AND ADVISE OF ANY CONFLICTS WITH PROPOSED UTILITIES. IF CONFLICTS ARE PRESENT. THE OWNER'S FIELD REPRESENTATIVE, JMC, PLLC AND THE APPLICABLE MUNICIPALITY OR AGENCY SHALL BE NOTIFIED IN WRITING. THE EXISTING/PROPOSED UTILITIES RELOCATION SHALL BE DESIGNED BY JMC, PLLC.
- 3. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY AND ALL LOCAL PERMITS REQUIRED.
- 4. ALL WORK SHALL BE DONE IN STRICT COMPLIANCE WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, STANDARDS, ORDINANCES, RULES AND REGULATIONS. ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL SAFETY CODES. APPLICABLE SAFETY CODES MEAN THE LATEST EDITION INCLUDING ANY AND ALL AMENDMENTS, REVISIONS, AND ADDITIONS THERETO, TO THE FEDERAL DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION'S OCCUPATIONAL SAFETY AND HEALTH STANDARDS (OSHA); AND APPLICABLE SAFETY, HEALTH REGULATIONS AND BUILDING CODES FOR CONSTRUCTION IN THE STATE OF NEW YORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR GUARDING AND PROTECTING ALL OPEN EXCAVATIONS IN ACCORDANCE WITH THE PROVISION OF SECTION 107-05 (SAFETY AND HEALTH REQUIREMENTS) OF THE NYSDOT STANDARD SPECIFICATIONS. IF THE CONTRACTOR PERFORMS ANY HAZARDOUS CONSTRUCTION PRACTICES. ALL OPERATIONS IN THE AFFECTED AREA SHALL BE DISCONTINUED AND IMMEDIATE ACTION SHALL BE TAKEN TO CORRECT THE SITUATION TO THE SATISFACTION OF THE APPROVAL AUTHORITY HAVING JURISDICTION.
- 5. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AFFECTED BY THE SCOPE OF WORK SHOWN HEREON AT ALL TIMES TO THE SATISFACTION OF THE OWNERS REPRESENTATIVE, RAMPING CONSTRUCTION TO PROVIDE ACCESS MAY BE CONSTRUCTED WITH SUBBASE MATERIAL EXCEPT THAT TEMPORARY ASPHALT CONCRETE SHALL BE PLACED AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FO PROVIDING SAFE PEDESTRIAN ACCESS AT ALL TIMES.
- 6. CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING PAVEMENT TO REMAIN.

AREA MAP SCALE: 1" = 100'

5,1	SUBS A COU RECC THE L UNDE GUAF OF AL OR C	URFACE UTILITY LOCATIONS ARE BASED ON MPILATION OF FIELD EVIDENCE, AVAILABLE ORD PLANS AND/OR UTILITY MARK-OUTS. COCATION OR COMPLETENESS OF REGROUND INFORMATION CANNOT BE RANTEED. VERIFY THE ACTUAL LOCATION L UTILITIES PRIOR TO EXCAVATION ONSTRUCTION.
R	No.	Revision
	1.	REVISED BUILDING FOOTPRINT
	2.	UPDATED WETLAND LINES
	3.	UPDATED SURVEY
	4.	REVISED PER VILLAGE COMMENTS
	5.	RESUBMIT TO VILLAGE HCZMC
	6.	RESPOND TO TOWN COMMENTS

RESUBMIT TO VILLAGE HCZMC Previous Editions Obsolete



JMC Drawing List:

C-000	COVER SHEET
C-010	EXISTING CONDITIONS MAP
C-020	DEMOLITION & TREE REMOVAL PLAN
C-100	LAYOUT PLAN
C-200	GRADING & UTILITY PLAN
C-300	EROSION & SEDIMENT CONTROL PLAN
C-900	CONSTRUCTION DETAILS
C-901	CONSTRUCTION DETAILS
C-902	CONSTRUCTION DETAILS
C-903	CONSTRUCTION DETAILS



TA SECTION 9, BLOCK 50, LOT 37 ZONE "R-20" - "ONE FAMILY PROPOSED USE: RESIDENTIAL FIRE DISTRICT: MAMARONECK WATER DISTRICT: WESTCHESTE SCHOOL DISTRICT: MAMARONE SEWER DISTRICT: PRIVATE ONS	ABLE OF L 73 RESIDENTIAL" VILLAGE FD R JOINT WATE CK SITE WASTEWA	AND USE R WORKS TER TREATMENT	r system	
DESCRIPTION		REQUIRED	EXISTING	PROPOSED
LOT AREA	(FEET)	20,000 MINIMUM	47,560 S.F.	47,560 S.F.
LOT WIDTH	(FEET)	100' MINIMUM	177'	177'
LOT FRONTAGE	(FEET)	100' MINIMUM	177'	177'
LOT DEPTH	(FEET)	100' MINIMUM	280'	280'
BUILDING HEIGHT	(STORIES/FEET)	2.5/35'	1.5/21'±	2.5/35'±
GROSS FLOOR AREA	(SQUARE FEET)	_	_	_
LOT COVERAGE BY PRINCIPAL BUILDING	(PERCENT)	35% MAXIMUM	3.4%	7.7%
OFF STREET PARKING SPACES	(EACH)	2	2	3
YARDS				
FRONT YARD SETBACK	(FEET)	25' MINIMUM	92'	90'
REAR YARD SETBACK	(FEET)	30' MINIMUM	162.9'	149'
SIDE YARD SETBACK	(FEET/TOTAL)	20' MIN/45' TOTAL	33.4'/93.8'	23.4'/56.3'
PARKING				
REAR/SIDE PARKING SETBACK	(FEET)	5' MINIMUM	26.7±	5'
TOTAL PARKING	(SPACES)	2 MINIMUM	1	3



04/11/2019

02/28/2020

05/11/2020

06/08/2020

07/01/2020

07/22/2020

09/02/2020

RAR





	LEGEND	프
	EXISTING PROPERTY LINE	
	ADJACENT PROPERTY LINE	SAF
	EXISTING EASEMENT LINE	
<u> </u>	EXISTING BUILDING LINE	
	EXISTING PAVEMENT EDGE	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
8	EXISTING CONTOUR	₹¥
10_	EXISTING INDEX CONTOUR	≶∑
XX	EXISTING FENCE	
	EXISTING FLAGGED WETLAND LINE	
(TIO M	EXISTING TREE AND DESIGNATION	Σ
	10 FOOT CONTOUR FROM USGS MAPPING (NYSDEC LIMIT OF ADJACENT AREA)	
	EXISTING WETLAND SETBACK	N
8" SAN	EXISTING SANITARY LINE AND SIZE	
WW	EXISTING WATER LINE	MF
—ОНW——ОНW—	EXISTING OVERHEAD WIRES	
0	EXISTING MANHOLE	
wv M	EXISTING WATER VALVE	
-0-	EXISTING UTILITY POLE	
◆ DP-2	BORING LOCATION AND DESIGNATION	dscal PLL(Nts, Ll
		 a g

<u>NOTES:</u>

- EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEE SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/2 04/23/2020.
- 2. WETLANDS FLAGGED BY ECOLOGICAL SOLUTIONS L.L.C.
- 3. THE MEAN LOW WATER BOUNDARY IS BEYOND DRAWING DELANCEY COVE CHANNEL.
- 4. MEAN HIGH WATER: 3.39' MEAN HIGHER HIGH WATER: 3.75' MEAN LOW WATER: -3.90 MEAN LOWER LOW WATER: -4.14

Revision

Previous Editions Obsolete

. REVISED BUILDING FOOTPRINT UPDATED WETLAND LINES

REVISED PER VILLAGE COMMENTS RESUBMIT TO VILLAGE HCZMC RESPOND TO TOWN COMMENTS RESUBMIT TO VILLAGE HCZMC

UPDATED SURVEY

ROPERTY LINE PROPERTY LINE ASEMENT LINE JILDING LINE AVEMENT EDGE ONTOUR DEX CONTOUR ENCE AGGED WETLAND LINE EE AND DESIGNATION NTOUR FROM USGS YSDEC LIMIT OF REA) ETLAND SETBACK ANITARY LINE AND SIZE ATER LINE	APPLICANT/OWNER: MR. WILLIAM FEDYNA & ELISABE FEDYNA 210 w BIST STREET ADT OD	ARCHITECT: ARCHI JOHN ST. #700 111 JOHN ST. #700 NEW YORK, NY 10038
ANHOLE ATER VALVE TILITY POLE CATION AND DESIGNATION PLAN HAVE BEEN TAKEN FROM G, DATED 02/22/2018, LAST REVISED TIONS L.L.C. OND DRAWING LIMITS TOWARD THE	JMC Planning, Engineering, Landscape Architecture & Land Surveying, PLLC JMC Site Development Consultants, LLC	Joint Weyer Consulting, Inc. 120 BEDFORD ROAD • ARMONK, NY 10504 voice 914.273.5225 • fax 914.273.2102 www.jmcpllc.com
	EXISTING CONDITIONS MAP	RESIDENTIAL DEVELOPMENT 1165 GREACEN POINT ROAD MAMARONECK, NY, 10543
ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.	EXISTING CONDITIONS MAP	RESIDENTIAL DEVELOPMENT 1165 GREACEN POINT ROAD MAMARONECK, NY, 10543



16" OAP

?" HICKORÝ

1[DITIONS	DEF	ICTED	ON	THIS	PLAN	HAVE	BEEN	TAKEN	FROM	SURVEN
Y	SPINEL	LI S	URVEY	1NG,	DATI	ED 02,	/22/20	018, L	AST RE	VISED	

2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UTILITIES TO BE DEMOLISHED AND EXISTING UTILITIES TO BE PROTECTED. IF ANY DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR AND JMC PRIOR TO THE START OF CONSTRUCTION.

3. PRIOR TO THE START OF ANY DEMOLITION THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND/OR APPROVALS FROM THE VILLAGE OF MAMARONECK AND ALL OTHER AUTHORITIES HAVING JURISDICTION. CONTRACTOR SHALL PAY ALL OUTSTANDING FEES, CHARGES, AND DEPOSITS TO ACQUIRE SAID PERMITS. NO DEMOLITION SHALL COMMENCE UNTIL A PERMIT HAS BEEN OBTAINED FROM

4. THE CONTRACTOR SHALL COORDINATE THE DISCONNECTION OF ALL UTILITIES WITH THE UTILITY COMPANY HAVING JURISDICTION PRIOR TO THE START OF DEMOLITION. CONFIRMATION OF DISCONNECTED UTILITIES SHALL BE PROVIDED TO THE VILLAGE OF MAMARONECK BUILDING DEPARTMENT IN ACCORDANCE WITH THEIR REQUIREMENTS. LETTERS FROM THE APPROPRIATE UTILITIES STATING THAT GAS AND ELECTRIC HAVE BEEN CUT OFF SHALL BE PROVIDED TO THE TOWN.

5. ANY UNSUITABLE MATERIAL FOUND ON-SITE DURING DEMOLITION/CONSTRUCTION, AS DETERMINED BY THE PROJECT'S GEOTECHNICAL ENGINEER, SHALL BE PROPERLY DISPOSED OF OFF-SITE IN A MANNER APPROVED BY ALL AUTHORITIES HAVING JURISDICTION AND REPLACED WITH SUITABLE MATERIAL AS REQUIRED.

6. ANY UNSUITABLE MATERIAL FOUND ON-SITE DURING CONSTRUCTION SHALL BE DISPOSED OF OFF-SITE IN A MANNER APPROVED BY ALL AUTHORITIES HAVING JURISDICTION AND REPLACED WITH SUITABLE MATERIAL AS REQUIRED. ALL REMOVAL AND REPLACEMENT OF UNSUITABLE MATERIAL SHALL BE COMPLETED UNDER THE DIRECT SUPERVISION OF A GEOTECHNICAL ENGINEER.

7. ALL DEMOLITION AND/OR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, INCLUDING STREETS AND SIDEWALKS, SHALL BE PERFORMED IN ACCORDANCE WITH THE

ALL CONSTRUCTION/DEMOLITION DEBRIS NOT PROPOSED TO BE RECYCLED SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF-SITE IN ACCORDANCE WITH THE REGULATIONS OF ALL LOCAL, STATE AND FEDERAL AGENCIES HAVING

9. EXISTING CONCRETE MAY BE STORED ON SITE, AND RECYCLED FOR USE AS COMPACTED FILL. ALL MATERIAL TO BE USED AS FILL SHALL BE APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER.

10. PRIOR TO THE START OF SITE DEMOLITION, EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THIS PLAN, AS REQUIRED AND/OR DIRECTED BY THE VILLAGE OF MAMARONECK OR JMC.

12. ALL EXISTING SIDEWALKS, CURBS, PAVEMENT, ETC. TO REMAIN, WHICH ARE DISTURBED OR DAMAGED DUE TO THE NEW CONSTRUCTION, ARE TO BE REPLACED

13. THESE PLANS ARE TO BE PROVIDED TO BOTH THE DEMOLITION CONTRACTOR AND THE SITE CONTRACTOR FOR THEIR USE, INFORMATION AND COORDINATION. ANY QUESTIONS OF CONTRACTOR RESPONSIBILITY AND/OR SEPARATION OF WORK SHALL BE DIRECTED TO THE GENERAL CONTRACTOR IN WRITING PRIOR TO

14. THE OWNER SHALL RETAIN A LICENSED AND QUALIFIED PROFESSIONAL, CERTIFIED BY THE TOWN, TO INSPECT FOR THE PRESENCE OF ASBESTOS AND/OR OTHER HAZARDOUS MATERIALS WITHIN DEMOLITION AREAS PRIOR TO THE COMMENCEMENT OF DEMOLITION. IF REMEDIATION IS REQUIRED, THE OWNER SHALL DO SO IN ACCORDANCE WITH THE COUNTY ASBESTOS RULES AND REGULATIONS AND/OR ANY AUTHORITIES HAVING JURISDICTION. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED DOCUMENTATION TO THE TOWN PRIOR TO OBTAINING A DEMOLITION

15. PRIOR TO COMMENCEMENT OF DEMOLITION, THE CONTRACTOR MUST PROVIDE

	LEGEND
	EXISTING PROPERTY LINE
	ADJACENT PROPERTY LINE
	EXISTING EASEMENT LINE
<u> </u>	EXISTING BUILDING LINE
	EXISTING PAVEMENT EDGE
	EXISTING CURB LINE
8	EXISTING CONTOUR
10_	EXISTING INDEX CONTOUR
XX	EXISTING FENCE
TTO W	EXISTING TREE AND DESIGNATION
TTO M	EXISTING TREE TO BE REMOVED
	EXISTING WETLAND SETBACK
36" RCP	EXISTING STORM DRAIN LINE AND SIZE
8" SAN	EXISTING SANITARY LINE AND SIZE
WW	EXISTING WATER LINE
OHWOHW	EXISTING OVERHEAD WIRES
0	EXISTING MANHOLE
WV X	EXISTING WATER VALVE
-0-	EXISTING UTILITY POLE
	EXISTING FEATURE TO BE REMOVED

PERTY LINE ROPERTY LINE REMENT LINE LDING LINE REMENT EDGE RB LINE REMENT EDGE RB LINE REMENT EDGE RB LINE REMOVED CE TO BE REMOVED LAND SETBACK RM DRAIN LINE AND SIZE	APPLICANTIOWNER: MR. WILLIAM FEDYNA & ELISABETH FEDYNA 219 w 81ST STREET, APT. 9D NEW YORK, NY, 10024 ARCHITECT: ARCHI- TECTONICS 111 JOHN ST. #700 NEW YORK, NY 10038
RHEAD WIRES HOLE TER VALVE JTY POLE TURE TO BE REMOVED	JMC Planning, Engineering, Landscape Architecture & Land Surveying, PLLC JMC Site Bevelopment Consultants, LLC John Meyer Consulting, Inc. 120 BEDF0RD R0AD • ARMONK, NY 10504 voice 914.273.5225 • fax 914.273.2102 www.jmcpllc.com
	DEMOLITION AND TREE REMOVAL PLAN RESIDENTIAL DEVELOPMENT 1165 GREACEN POINT ROAD MAMARONECK, NY, 10543
ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.	DEMOLITION AND TREE REMOVAL PLAN RESIDENTIAL DEVELOPMENT 1165 GREACEN POINT ROAD MAMARONECK, NY, 10543

Revision

Previous Editions Obsolete

REVISED BUILDING FOOTPRINT

REVISED PER VILLAGE COMMENTS

RESUBMIT TO VILLAGE HCZMC

RESPOND TO TOWN COMMENTS

RESUBMIT TO VILLAGE HCZMC

UPDATED WETLAND LINES

UPDATED SURVEY

DPYRGHT © 2019 by JMC All Rights Reserved. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by means, electronic, mechanical, biotopyrid, recording or otherwise, without the prior writing permission of JMC JANINIG, EALNING, EALNE, CHARTECTUPE RE, ALVID SURVING, PLLCI, JMC SITE DE REVELOPMENT Retrievants of the control of the prior of the prior of the control of the control of the control of the control of the prior of the prio



_ _ _ _ _ _ _ _



	LEGEND	║ ᡓ
	EXISTING PROPERTY LINE	
	ADJACENT PROPERTY LINE	II Y
	EXISTING SETBACK LINE	
<u> </u>	EXISTING BUILDING LINE	
	EXISTING PAVEMENT EDGE	
	EXISTING CURB LINE	
xx	EXISTING FENCE	EC STREET
(TIO M	EXISTING TREE AND DESIGNATION	
·~~·	EXISTING WATER LINE	
-0-	EXISTING UTILITY POLE	
	EXISTING WETLAND LIMITS	
	EXISTING WETLAND SETBACK	
	USGS 10 FOOT CONTOUR (NYSDEC JURISDICTIONAL LINE)	CT:
	EXISTING TREE TO REMAIN AND BE PROTECTED	
	PROPOSED BUILDING LINE	AR AR
	PROPOSED SAWCUT LINE	
	PROPOSED CONCRETE SIDEWALK	
	PROPOSED EDGE OF PAVEMENT	
	PROPOSED PAVEMENT HATCH	scape 2LLC 3, LLC 1050/ 3.2102
	PROPOSED RETAINING WALL (DESIGN BY OTHERS)	, Land ying, F sultant g, Inc. NK, NY 14.273
— x — x —	PROPOSED FENCE	leering d Surve nt Cons nsultin ARMO fax 9 plic.c
NOTES:		ing, Engir ure & Lan evelopme Meyer Co D ROAD • 73.5225 /w.jmc

 EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.

LOT COVERAGES						
WETLAND BUFFER	EXISTING	PROPOSED				
TOTAL WETLAND BUFFER COVERAGE	(S.F./PERCENT)	2,455±/6.6	5,427±/11.4			
LOT COVERAGE (PRINCIPAL BUILDING)	(S.F./PERCENT)	1,597±/3.4	3,459±/7.3			
LOT COVERAGE (SIDEWALK)	(S.F./PERCENT)	232±/0.05	200±/0.04			
LOT COVERAGE (DRIVEWAY)	(S.F./PERCENT)	626±/1.3	1,768±/3.7			
OVERALL SITE	EXISTING	PROPOSED				
OVERALL LOT COVERAGE	(S.F./PERCENT)	3,149±/6.6	6,480±/13.6			
LOT COVERAGE (PRINCIPAL BUILDING)	(S.F./PERCENT)	1,597±/3.4	3,655±/7.7			
LOT COVERAGE (SIDEWALK)	(S.F./PERCENT)	234±/0.05	499±/1.0			
LOT COVERAGE (DRIVEWAY)	(S.F./PERCENT)	1,318±/2.8	2,326±/4.9			

	Г						
		ANT A SPECI REPOI OF A LI ENGINI SURVE SECT YORK EXCEP SECTIO	IFICATION OF PI IFICATIONS, PLATS RTS BEARING THE CENSED PROFESS EER OR LICENSEE EYOR IS A VIOLATI FION 7209 OF THE STATE EDUCATION PT AS PROVIDED F ON 7209, SUBSECT	LANS, S AND SEAL SIONAL D LAND ON OF NEW N LAW, OR BY FION 2.			
D.	Revision		Date	Ву	Drawn:	RAR Appro	oved: JAR
.	REVISED BUILDING FOOTPRINT		04/11/2019	SPG	Scale:	1" = 20'	
. ।	UPDATED WETLAND LINES		02/28/2020	RC	Date:	07/24/2018	8
. ।	UPDATED SURVEY		05/11/2020	RAR	Project No:	18100	
.	REVISED PER VILLAGE COMMENTS		06/08/2020	RAR	18100-SITE	LAYOUT	LAY.scr
. I	RESUBMIT TO VILLAGE HCZMC		07/01/2020	RAR	Drawing No:		
.	RESPOND TO TOWN COMMENTS		07/22/2020	RAR		_1(\mathbf{D}
. I	RESUBMIT TO VILLAGE HCZMC		09/02/2020	RAR			JU
	Previous Editions Obsolete						

RESIDENTIAL DEVELOPMENT 1165 GREACEN POINT ROAD MAMARONECK, NY, 10543

PLAN

LAYOUT

(TYP. – 26,524± S.F.)

PROPOSED LIMIT

OF DISTURBANCE -

6" SDR-35 COLLECTOR PIPE FOR ROOF DRAIN LEADERS

PROPOSED SANITARY CLEAN

4" SDR-35 PVC —

1,250 GAL. SEPTIC TANK TOP 13.5' INV. IN 12.0' INV. OUT 11.75'

4" SDR-35 PVC -

LIMITS OF BANK SAND AND GRAVEL FILL MATERIAL

PROPOSED PRIMARY OWTS (340 LF PROVIDED) PROVIDE MINIMUM 3' RUN OF BANK SAND AND GRAVEL FILL MATERIAL

DISTRIBUTION BOX (TYP.) -

LIMITS OF IMPERVIOUS CLAY

PROPOSED 100% EXPANSION AREA (340 LF OF ABSORPTION TRENCH) APPLICANT IS REQUESTING A FILL WAIVER FOR THE EXPANSION AREA

FEMA ZONE AE13 -

16-ніскон

?" HICKORΎ



DSED GRADE) TW +	HBW (PROPOSED GRADE)
FILL REQUIRED FO	OR SITE (CUBIC YARDS)
NK FILL (SEPTIC AREA)	480
CLAY FILL (SEPTIC AREA)	93
DRIVEWAY	58
R HARVESTING TANKS	24
ER DETENTION AREA	63
(EXCLUDING SEPTIC AREA)	35
(EXCLUDING SEPTIC AREA)	343
DTAL NET FILL	1,096

	LEGEND		È			
	EXISTING PROPERTY LINE		Ш			
	ADJACENT PROPERTY LINE		β			
	EXISTING EASEMENT LINE				0 6	
	EXISTING BUILDING OVERHANG		Ē		7. 1.	S S
//////////////////////////////////////	EXISTING BUILDING LINE		న		1001	
	EXISTING PAVEMENT EDGE		A	AN	Ľ. Ţ	CT(
8	EXISTING CONTOUR		X	\succeq	STR , N	
10_	EXISTING INDEX CONTOUR				ST ST	
-xx	EXISTING FENCE		L L		× 00	H H H H H H H H H H H H H H H H H H H
0	EXISTING MANHOLE		AN		≥ Ú N O	AR
\bowtie	EXISTING WATER VALVE				21	
-0-	EXISTING UTILITY POLE		MAT/OW			Ë
	EXISTING SANITARY LINE		Ч СЧ СЧ СЧ			HITEO
WWWW	EXISTING WATER LINE					ARC
GGGG	EXISTING GAS LINE					
	EXISTING WETLAND LIMITS					
_	EXISTING WETLAND SETBACK					
	USGS 10 FOOT CONTOUR (NYSDEC JURISDICTIONAL LINE)		icape ILC	- s, LLC	i	10504 .2102
	PROPOSED BUILDING LINE		ands 1g, P	tant	Inc.	, NY .273
	PROPOSED ASPHALT		ı <mark>g, L</mark> veyin	nsu	ing,	914 914
	PROPOSED PAVER WALKWAY		neerir 1d Sur	ent Co	onsult	• ARM • fax
13	PROPOSED FINISHED GRADE		l, Engi & Lai	lopme	yer C	10AD .5225
13.50 +	PROPOSED SPOT GRADE		ming sture	Deve	n Mŧ	RD F .273
	PROPOSED RETAINING WALL (DESIGN BY OTHERS)		C Plan chiteo	Site	Joh	EDF0 e 914
● CO	PROPOSED CLEANOUT		JM(Are	JMC		20 B voic
2" WATER	PROPOSED WATER LINE & SIZE					/
I	PROPOSED WATER VALVE					
0	PRIMARY OWTS FIELD WITH DISTRIBUTION BOX	H	_			
	EXPANSION FIELD					
	PROPOSED 1,500 GAL. SEPTIC TANK					
		<u>'</u>				

<u>NOTES:</u>

- 1. EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.
- 2. ALL FILLS SHALL BE COMPACTED TO PROVIDE STABILITY OF MATERIAL AND TO PREVENT SETTLEMENT. 3. EXCAVATIONS AND FILLS SHALL NOT ENDANGER ADJOINING PROPERTIES, NOR DIVERT WATER ONTO THE PROPERTY OF OTHERS AT ANY TIME DURING THE
- COURSE OF CONSTRUCTION. 4. CONTRACTOR SHALL REFER TO EROSION AND SEDIMENT CONTROL PLAN FOR FURTHER DIRECTION REGARDING SITE STABILIZATION THROUGHOUT THE COURSE OF CONSTRUCTION.
- 5. UNLESS OTHERWISE SPECIFIED, PIPE FOR WATER LINES SHALL TYPE 'K' COPPER TUBE IN ACCORDANCE WITH ASTM B-88.

Ζ

 \triangleleft

Δ

 \supset

ઝ

-OPMEN ROAD 10543

EVEL POINT NY, 10

SIDENTIAL 1165 GREACI MAMARONE

6. ELECTRIC, TELEPHONE, AND CABLE TELEVISION LINES SHALL BE INSTALLED UNDERGROUND IN CONDUIT IN ACCORDANCE WITH THE REQUIREMENTS OF THE UTILITY COMPANY HAVING JURISDICTION.

				GRADING	RESIDEN 1165
	ANV SPE REP OF A ENG SUR SUR SUR SEC	ALTERATION OF P CIFICATIONS, PLAT ORTS BEARING THE LICENSED PROFES NEER OR LICENSEI /EYOR IS A VIOLAT CTION 7209 OF THE & STATE EDUCATIO EPT AS PROVIDED F FION 7209, SUBSEC	LANS, S AND E SEAL SIONAL D LAND ION OF NEW N LAW, FOR BY TION 2.		
No.	Revision	Date	Ву	Drawn: RAR	Approved: JAR
1.	REVISED BUILDING FOOTPRINT	04/11/2019	SPG	Scale: 1" =	20'
2.	UPDATED WETLAND LINES	02/28/2020	RC	Date: 07/2	4/2018
3.	UPDATED SURVEY	05/11/2020	RAR	Project No: 18100	
4.	REVISED PER VILLAGE COMMENTS	06/08/2020	RAR	18100-SITE GRAI) UTIL GRADUTIL.se
5.	RESUBMIT TO VILLAGE HCZMC	07/01/2020	RAR	Drawing No:	
6.	RESPOND TO TOWN COMMENTS	07/22/2020	RAR		$2 \cap \cap$
7.	RESUBMIT TO VILLAGE HCZMC	09/02/2020	RAR		ZUU
	Previous Editions Obsolete				

PROPOSED LIMIT OF DISTURBANCE (TYP. - 26,524± S.F.)

PROPOSED DOUBLE

ROW OF SILT FENCE

PROPOSED SILT FENCE (TYP.)

PROPOSED TREE PROTECTION (TYP.)

FENCE OFF PROPOSED SEPTIC AREA W/TEMPORARY CONSTRUCTION FENCE. CONSTRUCTION ACTIVITY IN THIS AREA SHALL BE LIMITED TO THE CONSTRUCTION OF THE SEPTIC & COMPONENTS

> PROPOSED SOIL STOCKPILE WITH DOUBLE ROW OF SILT FENCE EXISTING TREES TO REMAIN AND BE PROTECTED (TYP.)



SEQUENCE	OF	CONSTRUCTION
----------	----	---------------------

CONSTRUCTION SHALL BE SEQUENCED IN SUCH A MANNER THAT ANY AREA WHICH IS DISTURBED SHALL FIRST BE PROTECTED WITH SEDIMENT EROSION CONTROLS AS INDICATED ON THIS PLAN. PARTICULAR REQUIREMENTS ARE GIVEN

1. DEMOLITION OF EXISTING BUILDINGS AS REQUIRED.

2. INSTALLATION OF SEDIMENT AND EROSION CONTROL MEASURES AS INDICATED 3. CLEAR UNDEVELOPED PORTION OF PROPERTY WHICH IS TO BE DEVELOPED.

5. BEGIN BUILDING AND PARKING LOT CONSTRUCTION, ROUGH GRADING. 6. INSTALL STORM DRAIN SYSTEM COMPLETE (IMMEDIATELY INSTALL HAYBALE

7. INSTALL PUBLIC UTILITIES (GAS, ELECTRIC AND TELEPHONE) AS REQUIRED.

8. INSTALL CONCRETE AND ASPHALT CONCRETE PAVEMENT COMPLETE. 9. FINISH GRADING, REDISTRIBUTE TOPSOIL AND ESTABLISH VEGETATION AND/OR

10. CLEAN PAVEMENTS AND STORM DRAIN SYSTEM OF ALL ACCUMULATED SEDIMENT IN CONJUNCTION WITH THE REMOVAL OF ALL TEMPORARY SEDIMENT AND

TROL	DEVI	CES.	
E AN	D BU	ILDING	CONSTRUCTION.

LEGEND					
	EXISTING WETLAND SETBACK				
	PROPOSED SILT FENCE				
·	PROPOSED LIMIT OF DISTURBANCE				
	PROPOSED CONSTRUCTION FENCE				
	PROPOSED STABILIZED CONSTRUCTION ENTRANCE				
	PROPOSED STOCKPILE AREA				

Ш

S

ઝ

WILLIAM

N N

S

Ο

 \mathcal{L} Ш

SEDIMEN⁻ PLAN

SION &

 \bigcirc

DEVELOPMENT EN POINT ROAD CK, NY, 10543

SIDENTIAL 1165 CREACE MAMARONEC

RE

Δ

σ

2

⊢<u></u>40

70

20

AR(NE)

 $\bigcirc \#$

<u>NOTES:</u>

- EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.
- THIS PLAN IS FOR TEMPORARY EROSION AND SEDIMENT CONTROL INFORMATION ONLY.
- PRIOR TO BEGINNING ANY CLEARING, GRUBBING OR EXCAVATION, ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH ALL THE PLANS AND SPECIFICATIONS. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL THE SITE IS STABILIZED. FINAL STABILIZATION OF LANDSCAPED AREAS SHALL BE IN ACCORDANCE WITH THE LANDSCAPE PLAN.
- 4. THE CONTRACTOR SHALL INSPECT AND MAINTAIN ON-SITE EROSION AND SEDIMENT CONTROL MEASURES ON A DAILY BASIS. ALL COLLECTED SEDIMENT WITHIN SEDIMENT BARRIERS SHALL BE REMOVED PERIODICALLY AS REQUIRED TO MAINTAIN THE FUNCTION OF THE SEDIMENT BARRIERS. ALL SEDIMENT COLLECTED SHALL BE RESPREAD ON-SITE WITHIN STABILIZED AREAS AS DIRECTED BY THE OWNERS REPRESENTATIVE.
- 5. THE CONTRACTOR SHALL INSPECT DOWNSTREAM CONDITIONS FOR EVIDENCE OF SEDIMENTATION ON A WEEKLY BASIS, AFTER EACH RAINSTORM, AND AS MAY BE REQUIRED OR DIRECTED BY ALL APPLICABLE APPROVALS AND PERMITS. THE CONTRACTOR SHALL IMMEDIATELY PROVIDE A WRITTEN REPORT ON FINDINGS OF SEDIMENT IN DOWNSTREAM AREAS TO ALL AUTHORITIES HAVING JURISDICTION AND MAKE REPAIRS AS REQUIRED OR DIRECTED.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED BY THE CONTRACTOR AS REQUIRED/WARRANTED BY FIELD CONDITIONS AND AS DIRECTED BY THE OWNERS REPRESENTATIVE, JMC, AND/OR ANY AUTHORITY HAVING JURISDICTION.
- 7. STOCKPILING OF CONSTRUCTION MATERIAL SHALL BE PLACED ON-SITE IN THE AREA DESIGNATED ON THIS PLAN OR AS APPROVED BY THE OWNERS REPRESENTATIVE. STOCKPILED EXCAVATED MATERIAL SHALL HAVE TWO ROWS OF SILT FENCE LOCATED AROUND ITS PERIMETER. ALL STOCKPILED MATERIAL SHALL BE MAINTAINED IN AN ORDERLY MANNER SO AS NOT TO IMPEDE ON PEDESTRIAN AND/OR VEHICULAR TRAFFIC CIRCULATION ROUTES.
- 7. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OWNERS REPRESENTATIVE.
- 8. ALL STORMWATER MANAGEMENT PRACTICES SHALL REMAIN UNDISTURBED AND BE PROTECTED FROM HEAVY MACHINERY TRAFFIC DURING CONSTRUCTION. HOWEVER DURING CONSTRUCTION OF THE PRACTICE THE CONTRACTOR SHALL MINIMIZE AND AVOID HEAVY MACHINERY TRAFFIC TO THE MAXIMUM EXTENT PRACTICABLE. THERE SHALL BE NO STORAGE OF MATERIALS WITHIN AREAS TO BE USED FOR STORMWATER MANAGEMENT PRACTICES. THE CONTRACTOR SHALL INSTALL CONSTRUCTION FENCE AROUND THE PRACTICE TO DISCOURAGE VEHICLE TRAFFIC.
- 9. ALL EXPOSED SLOPES AND GRADED/DISTURBED AREAS, THAT WILL NOT BE FURTHER DISTURBED WITHIN 14 CALENDAR DAYS (7 DAYS FOR CONSTRUCTION SITES THAT EITHER DIRECTLY DISCHARGE TO ONE OF THE 303(d) SEGMENTS LISTED IN APPENDIX E OF THE GENERAL PERMIT OR ARE LOCATED WITHIN ONE OF THE WATERSHEDS LISTED IN APPENDIX C OF THE GENERAL PERMIT), SHALL BE TEMPORARILY SEEDED WITHIN 24 HOURS OF DISTURBANCE, IN ACCORDANCE WITH THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION (NYSDEC) "EROSION AND SEDIMENT CONTROL GUIDELINES" AND THE ANSI A300 "BEST MANAGEMENT PRACTICES FOR TREE AND SHRUB PLANTING, TRANSPLANTING, MAINTENANCE AND CARE," PREPARED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE (ISA), LATEST EDITIONS, AS FOLLOWS:
- A. SEED MIXTURE AND RATE OF APPLICATION:
- A.1. IN SPRING, SUMMER OR EARLY FALL, SEED THE AREA WITH RYEGRASS (ANNUAL OR PERENNIAL) AT 30 POUNDS PER ACRES (APPROXIMATELY 0.7 POUNDS/1000 SQUARE FEET OR USE 1 POUND/1000 SQUARE FEET).
- A.2. IN LATÉ FALL OR EARLY WINTER, SEED THE AREA WITH CERTIFIED 'AROOSTOOK' WINTER RYE (CEREAL RYE) AT 100 POUNDS PER ACRE (2.5 POUNDS/1000 SQUARE FEET).
- B. APPLICATION SHALL BE UNIFORM BY MECHANICAL OR HYDROSEED METHODS.
- C. MULCH ALL SEEDED AREAS WITH STRAW AT A RATE OF 2 TONS PER ACRE (90 POUNDS PER 1,000 SQUARE FEET) SUCH THAT THE MULCH FORMS A CONTINUOUS BLANKET.
- 10. ALL SEEDED AREAS SHALL BE FERTILIZED, RESEEDED, AND MULCHED AS NECESSARY TO MAINTAIN VIGOROUS, DENSE VEGETATIVE COVER.
- 11. TEMPORARY SEED MIXTURES SHALL NOT BE PLACED ON AREAS WHERE FINAL GRADE HAS BEEN ESTABLISHED AND TOPSOIL HAS BEEN PLACED UNLESS OTHERWISE DIRECTED BY THE PROJECT LANDSCAPE ARCHITECT.

		ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.					
No.	Revision		Date	Ву	Drawn:	RAR App	roved: JAR
1.	REVISED BUILDING FOOTPRINT		04/11/2019	SPG	Scale:	1'' = 20'	
2.	UPDATED WETLAND LINES			RC	Date:	07/24/2018	
3.	UPDATED SURVEY		05/11/2020	RAR	Project No:	18100	
4.	REVISED PER VILLAGE COMMENTS		06/08/2020	RAR	18100-SITE	SE	SE.scr
5.	RESUBMIT TO VILLAGE HCZMC		07/01/2020	RAR	Drawing No:		
6.	RESPOND TO TOWN COMMENTS		07/22/2020	RAR		71	$\gamma \gamma$
7.	RESUBMIT TO VILLAGE HCZMC		09/02/2020	RAR	ーし	- 31	JU
	Previous Editions Obsolete					-	





GHT © 2020 by JMC AI Rights Reserved. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by means, electronic, mechanical 19, recording or otherwise, without the prior written permission of JMC PLANNING, ENGINEERING, LANDSCAPE ARCHITECTURE & LAND SURVEYING, PLLC | JMC SITE DEVELOPIN WTS, LLC | JOHN MEYER CONSULTING, INC, (JMC). Any modifications or alterations to this document without the written permission of JMC shall ender them invalid and urusable.