SITE PLAN APPROVAL DRAWINGS

RESIDENTIAL DEVELOPMENT

TAX MAP SECTION 9 | BLOCK 50 | LOT 373
WESTCHESTER COUNTY
1165 GREACEN POINT ROAD
MAMARONECK, NY, 10543

Applicant/Owner:

MR. WILLIAM FEDYNA & ELISABETH FEDYNA
219 W 81ST STREET, APT. 9D
NEW YORK, NY. 10024

Architect:

ARCHI-TECTONICS

111 JOHN ST #700 NEW YORK, NY 10038 (212)206-0920

Attorney:

CUDDY & FEDER LLP 445 HAMILTON AVENUE, 14TH FLOOR WHITE PLAINS, NY 10601 (914)761-1300


Surveyor:


SPINELLI SURVEYING


650 HALSTEAD AVENUE MAMARONECK, NY 10543 (914) 381-2357



Site Planner, Civil & Traffic Engineer,
Surveyor and Landscape Architect:
120 BEDFORD ROAD
ARMONK, NY 10504
(914) 273-5225







PROJECT AREA

GENERAL CONSTRUCTION NOTES APPLY TO ALL WORK HEREIN:

- 1. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CALL 811 "DIG SAFELY" (1-800-962-7962) TO HAVE UNDERGROUND UTILITIES LOCATED. EXPLORATORY EXCAVATIONS SHALL COMPLY WITH CODE 753 REQUIREMENTS. NO WORK SHALL COMMENCE UNTIL ALL THE OPERATORS HAVE NOTIFIED THE CONTRACTOR THAT THEIR UTILITIES HAVE BEEN LOCATED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PRESERVATION OF ALL PUBLIC AND PRIVATE UNDERGROUND AND SURFACE UTILITIES AND STRUCTURES AT OR ADJACENT TO THE SITE OF CONSTRUCTION, INSOFAR AS THEY MAY BE ENDANGERED BY THE CONTRACTOR'S OPERATIONS. THIS SHALL HOLD TRUE WHETHER OR NOT THEY ARE SHOWN ON THE CONTRACT DRAWINGS. IF THEY ARE SHOWN ON THE DRAWINGS, THEIR LOCATIONS ARE NOT GUARANTEED EVEN THOUGH THE INFORMATION WAS OBTAINED FROM THE BEST AVAILABLE SOURCES, AND IN ANY EVENT, OTHER UTILITIES ON THESE PLANS MAY BE ENCOUNTERED IN THE FIELD. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, IMMEDIATELY REPAIR OR REPLACE ANY STRUCTURES OR UTILITIES THAT HE DAMAGES, AND SHALL CONSTANTLY PROCEED WITH CAUTION TO PREVENT UNDUE INTERRUPTION OF UTILITY SERVICE.
- 2. CONTRACTOR SHALL HAND DIG TEST PITS TO VERIFY THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR SHALL VERIFY EXISTING UTILITIES DEPTHS AND ADVISE OF ANY CONFLICTS WITH PROPOSED UTILITIES. IF CONFLICTS ARE PRESENT. THE OWNER'S FIELD REPRESENTATIVE, JMC, PLLC AND THE APPLICABLE MUNICIPALITY OR AGENCY SHALL BE NOTIFIED IN WRITING. THE EXISTING/PROPOSED UTILITIES RELOCATION SHALL BE DESIGNED BY JMC, PLLC.
- 3. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY AND ALL LOCAL PERMITS REQUIRED.
- 4. ALL WORK SHALL BE DONE IN STRICT COMPLIANCE WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, STANDARDS, ORDINANCES, RULES, AND REGULATIONS. ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL SAFETY CODES. APPLICABLE SAFETY CODES MEAN THE LATEST EDITION INCLUDING ANY AND ALL AMENDMENTS, REVISIONS, AND ADDITIONS THERETO, TO THE FEDERAL DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION'S OCCUPATIONAL SAFETY AND HEALTH STANDARDS (OSHA); AND APPLICABLE SAFETY, HEALTH REGULATIONS AND BUILDING CODES FOR CONSTRUCTION IN THE STATE OF NEW YORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR GUARDING AND PROTECTING ALL OPEN EXCAVATIONS IN ACCORDANCE WITH THE PROVISION OF SECTION 107–05 (SAFETY AND HEALTH REQUIREMENTS) OF THE NYSDOT STANDARD SPECIFICATIONS. IF THE CONTRACTOR PERFORMS ANY HAZARDOUS CONSTRUCTION PRACTICES, ALL OPERATIONS IN THE AFFECTED AREA SHALL BE DISCONTINUED AND IMMEDIATE ACTION SHALL BE TAKEN TO CORRECT THE SITUATION TO THE SATISFACTION OF THE APPROVAL AUTHORITY HAVING JURISDICTION.
- 5. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AFFECTED BY THE SCOPE OF WORK SHOWN HEREON AT ALL TIMES TO THE SATISFACTION OF THE OWNERS REPRESENTATIVE. RAMPING CONSTRUCTION TO PROVIDE ACCESS MAY BE CONSTRUCTED WITH SUBBASE MATERIAL EXCEPT THAT TEMPORARY ASPHALT CONCRETE SHALL BE PLACED AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE PEDESTRIAN ACCESS AT ALL TIMES.
- 6. CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING PAVEMENT TO REMAIN.

JMC Drawing List:

C-000 COVER SHEET

C-010 EXISTING CONDITIONS MAP

C-020 DEMOLITION & TREE REMOVAL PLAN

C-100 LAYOUT PLAN

C-200 GRADING & UTILITY PLAN

C-300 EROSION & SEDIMENT CONTROL PLAN

C-900 CONSTRUCTION DETAILS
C-901 CONSTRUCTION DETAILS

C-902 CONSTRUCTION DETAILS

C-903 CONSTRUCTION DETAILS

L-100 LANDSCAPING & WETLAND MITIGATION PLAN

TABLE OF LAND USE

SECTION 9, BLOCK 50, LOT 373

ZONE "R-20" - "ONE FAMILY RESIDENTIAL"


OPOSED USE: RESIDENTIAL


INE DISTRICT: MAMARONECK VILLAGE PU NATED DISTRICT: WESTCHESTED IONIT WATED WORKS

CHOOL DISTRICT MAMARONECI

EWER DISTRICT: PRIVATE ONSITE WASTEWATER TREATMENT SYSTEM

| SEWER DISTRICT: PRIVATE ON | SIIE WASIEWAI | IER IREAIMENI | SYSIEM | |
|------------------------------------|----------------|-------------------|-------------|-------------|
| DESCRIPTION | | REQUIRED | EXISTING | PROPOSED |
| LOT AREA | (FEET) | 20,000 MINIMUM | 47,560 S.F. | 47,560 S.F. |
| LOT WIDTH | (FEET) | 100' MINIMUM | 177' | 177' |
| LOT FRONTAGE | (FEET) | 100' MINIMUM | 177' | 177' |
| LOT DEPTH | (FEET) | 100' MINIMUM | 280' | 280' |
| BUILDING HEIGHT | (STORIES/FEET) | 2.5/35' | 1.5/21'± | 2.5/35'± |
| GROSS FLOOR AREA | (SQUARE FEET) | _ | _ | _ |
| LOT COVERAGE BY PRINCIPAL BUILDING | (PERCENT) | 35% MAXIMUM | 3.4% | 7.7% |
| OFF STREET PARKING SPACES | (EACH) | 2 | 2 | 3 |
| YARDS | | | | |
| FRONT YARD SETBACK | (FEET) | 25' MINIMUM | 92' | 90' |
| REAR YARD SETBACK | (FEET) | 30' MINIMUM | 162.9' | 149' |
| SIDE YARD SETBACK | (FEET/TOTAL) | 20' MIN/45' TOTAL | 33.4'/93.8' | 23.4'/56.3' |
| PARKING | | | | |
| REAR/SIDE PARKING SETBACK | (FEET) | 5' MINIMUM | 26.7± | 5' |
| TOTAL PARKING | (SPACES) | 2 MINIMUM | 1 | 3 |







| No. | Revision | Date | Ву |
|-----|------------------------------|------------|-----|
| 1. | REVISED BUILDING FOOTPRINT | 04/11/2019 | SPG |
| 2. | UPDATED WETLAND LINES | 02/28/2020 | RC |
| 3. | UPDATED SURVEY | 05/11/2020 | RAR |
| 4. | REVISED PER VILLAGE COMMENTS | 06/08/2020 | RAR |
| 5. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR |
| 6. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR |
| 7. | RESUBMIT TO VILLAGE HCZMC | 09/02/2020 | RAR |
| | Provious Editions Obsolete | | |



ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

JMC Planning, Engineering, Landscape
Architecture & Land Surveying, PLLC

JMC Site Development Consultants, LLC

John Meyer Consulting, Inc.

 Drawn:
 RAR
 Approved:
 JAR

 Scale:
 NOT TO SCALE

 Date:
 07/24/2018

 Project No:
 18100


120 BEDFORD ROAD • ARMONK, NY 10504 voice 914.273.5225 • fax 914.273.2102

www.jmcpllc.com

C-000

COVER COVER.scr






- SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED
- 2. WETLANDS FLAGGED BY ECOLOGICAL SOLUTIONS L.L.C.
- THE MEAN LOW WATER BOUNDARY IS BEYOND DRAWING LIMITS TOWARD THE DELANCEY COVE CHANNEL.
- 4. MEAN HIGH WATER: 3.39' MEAN HIGHER HIGH WATER: 3.75'
 MEAN LOW WATER: -3.90
 MEAN LOWER LOW WATER: -4.14

NOTES:

1. EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM

ABE

ELIS/




DEVELOPMENT CEN POINT ROAD ECK, NY, 10543 CONDITIONS

RESIDENTIAL 1165 GREACE MAMARONEC

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

| No. | Revision | Date | Ву |
|-----|------------------------------|------------|-----|
| 1. | REVISED BUILDING FOOTPRINT | 04/11/2019 | SPG |
| 2. | UPDATED WETLAND LINES | 02/28/2020 | RC |
| 3. | UPDATED SURVEY | 05/11/2020 | RAR |
| 4. | REVISED PER VILLAGE COMMENTS | 06/08/2020 | RAR |
| 5. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR |
| 6. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR |
| 7. | RESUBMIT TO VILLAGE HCZMC | 09/02/2020 | RAR |
| | Previous Editions Obsolete | | |
| | · | • | |

| Ву | Drawn: | RAR Appro | oved: JAR |
|-----|--------------|------------|-----------|
| | Scale: | 1" = 20' | |
| SPG | | 1 = 20 | |
| RC | Date: | 07/24/2018 | 8 |
| RAR | Project No: | 18100 | |
| RAR | 18100-SITE | EXIST | EXIST.scr |
| RAR | Drawing No: | L | .L |
| RAR | | 1 | |
| RAR | - | -U | IU |



- 1. EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED
- 2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UTILITIES TO BE DEMOLISHED AND EXISTING UTILITIES TO BE PROTECTED. IF ANY DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR AND JMC PRIOR TO THE START OF CONSTRUCTION.
- 3. PRIOR TO THE START OF ANY DEMOLITION THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND/OR APPROVALS FROM THE VILLAGE OF MAMARONECK AND ALL OTHER AUTHORITIES HAVING JURISDICTION. CONTRACTOR SHALL PAY ALL OUTSTANDING FEES, CHARGES, AND DEPOSITS TO ACQUIRE SAID PERMITS. NO DEMOLITION SHALL COMMENCE UNTIL A PERMIT HAS BEEN OBTAINED FROM
- 4. THE CONTRACTOR SHALL COORDINATE THE DISCONNECTION OF ALL UTILITIES WITH THE UTILITY COMPANY HAVING JURISDICTION PRIOR TO THE START OF DEMOLITION. CONFIRMATION OF DISCONNECTED UTILITIES SHALL BE PROVIDED TO THE VILLAGE OF MAMARONECK BUILDING DEPARTMENT IN ACCORDANCE WITH THEIR REQUIREMENTS. LETTERS FROM THE APPROPRIATE UTILITIES STATING THAT GAS AND ELECTRIC HAVE BEEN CUT OFF SHALL BE PROVIDED TO THE TOWN.
- 5. ANY UNSUITABLE MATERIAL FOUND ON-SITE DURING DEMOLITION/CONSTRUCTION, AS DETERMINED BY THE PROJECT'S GEOTECHNICAL ENGINEER, SHALL BE PROPERLY DISPOSED OF OFF-SITE IN A MANNER APPROVED BY ALL AUTHORITIES HAVING JURISDICTION AND REPLACED WITH SUITABLE MATERIAL AS REQUIRED.
- 6. ANY UNSUITABLE MATERIAL FOUND ON-SITE DURING CONSTRUCTION SHALL BE DISPOSED OF OFF-SITE IN A MANNER APPROVED BY ALL AUTHORITIES HAVING JURISDICTION AND REPLACED WITH SUITABLE MATERIAL AS REQUIRED. ALL REMOVAL AND REPLACEMENT OF UNSUITABLE MATERIAL SHALL BE COMPLETED UNDER THE DIRECT SUPERVISION OF A GEOTECHNICAL ENGINEER.
- 7. ALL DEMOLITION AND/OR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, INCLUDING STREETS AND SIDEWALKS, SHALL BE PERFORMED IN ACCORDANCE WITH THE
- BE REMOVED AND LEGALLY DISPOSED OF OFF-SITE IN ACCORDANCE WITH THE REGULATIONS OF ALL LOCAL, STATE AND FEDERAL AGENCIES HAVING 9. EXISTING CONCRETE MAY BE STORED ON SITE, AND RECYCLED FOR USE AS
- COMPACTED FILL. ALL MATERIAL TO BE USED AS FILL SHALL BE APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER. 10. PRIOR TO THE START OF SITE DEMOLITION, EROSION AND SEDIMENT CONTROL
- DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THIS PLAN, AS REQUIRED AND/OR DIRECTED BY THE VILLAGE OF MAMARONECK OR JMC. 11. EXISTING DRAINAGE PATTERNS ON SITE SHALL BE MAINTAINED TO THE MAXIMUM
- EXTENT PRACTICABLE. 12. ALL EXISTING SIDEWALKS, CURBS, PAVEMENT, ETC. TO REMAIN, WHICH ARE DISTURBED OR DAMAGED DUE TO THE NEW CONSTRUCTION, ARE TO BE REPLACED
- WITH MATERIALS CONSISTENT WITH EXISTING CONDITIONS. 13. THESE PLANS ARE TO BE PROVIDED TO BOTH THE DEMOLITION CONTRACTOR AND THE SITE CONTRACTOR FOR THEIR USE, INFORMATION AND COORDINATION. ANY QUESTIONS OF CONTRACTOR RESPONSIBILITY AND/OR SEPARATION OF WORK
- 14. THE OWNER SHALL RETAIN A LICENSED AND QUALIFIED PROFESSIONAL, CERTIFIED BY THE TOWN, TO INSPECT FOR THE PRESENCE OF ASBESTOS AND/OR OTHER HAZARDOUS MATERIALS WITHIN DEMOLITION AREAS PRIOR TO THE COMMENCEMENT OF DEMOLITION. IF REMEDIATION IS REQUIRED, THE OWNER SHALL DO SO IN ACCORDANCE WITH THE COUNTY ASBESTOS RULES AND REGULATIONS AND/OR ANY AUTHORITIES HAVING JURISDICTION. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED DOCUMENTATION TO THE TOWN PRIOR TO OBTAINING A DEMOLITION

SHALL BE DIRECTED TO THE GENERAL CONTRACTOR IN WRITING PRIOR TO

ISSUANCE OF BID.

15. PRIOR TO COMMENCEMENT OF DEMOLITION, THE CONTRACTOR MUST PROVIDE 24-HOUR NOTIFICATION TO THE TOWN.

ELIS,

LEGEND

EXISTING PROPERTY LINE

ADJACENT PROPERTY LINE

EXISTING EASEMENT LINE

EXISTING BUILDING LINE

EXISTING PAVEMENT EDGE

EXISTING INDEX CONTOUR

EXISTING TREE AND DESIGNATION

EXISTING TREE TO BE REMOVED

EXISTING WETLAND SETBACK

EXISTING WATER LINE

EXISTING MANHOLE

EXISTING WATER VALVE

EXISTING UTILITY POLE

EXISTING OVERHEAD WIRES

EXISTING STORM DRAIN LINE AND SIZE

EXISTING SANITARY LINE AND SIZE


EXISTING FEATURE TO BE REMOVED

EXISTING CURB LINE

EXISTING CONTOUR

EXISTING FENCE

—OHW——OHW—





AND PL DEMOLITION / TREE REMOVAL RESIDENTIAL 1165 GREACE MAMARONEC

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

| No. | Revision | Date | Ву | Dr Sc |
|-----|------------------------------|------------|-----|----------|
| 1. | REVISED BUILDING FOOTPRINT | 04/11/2019 | SPG | I L |
| 2. | UPDATED WETLAND LINES | 02/28/2020 | RC | Da |
| 3. | UPDATED SURVEY | 05/11/2020 | RAR | Pr |
| 4. | REVISED PER VILLAGE COMMENTS | 06/08/2020 | RAR | 1 |
| 5. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR | Dr |
| 6. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR | |
| 7. | RESUBMIT TO VILLAGE HCZMC | 09/02/2020 | RAR | |
| | Previous Editions Obsolete | | · | JL |
| | <u> </u> | <u> </u> | | |

Drawn: RAR Approved: JAR Scale: 1" = 20' 07/24/2018





NOTES

 EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.


| LOT COVERAGES | | | | | | |
|-----------------------------------|----------------|------------|-------------|--|--|--|
| WETLAND BUFFE | R | EXISTING | PROPOSED | | | |
| TOTAL WETLAND BUFFER COVERAGE | (S.F./PERCENT) | 2,455±/6.6 | 5,427±/11.4 | | | |
| LOT COVERAGE (PRINCIPAL BUILDING) | (S.F./PERCENT) | 1,597±/3.4 | 3,459±/7.3 | | | |
| LOT COVERAGE (SIDEWALK) | (S.F./PERCENT) | 232±/0.05 | 200±/0.04 | | | |
| LOT COVERAGE (DRIVEWAY) | (S.F./PERCENT) | 626±/1.3 | 1,768±/3.7 | | | |
| OVERALL SITE | | EXISTING | PROPOSED | | | |
| OVERALL LOT COVERAGE | (S.F./PERCENT) | 3,149±/6.6 | 6,480±/13.6 | | | |
| LOT COVERAGE (PRINCIPAL BUILDING) | (S.F./PERCENT) | 1,597±/3.4 | 3,655±/7.7 | | | |
| LOT COVERAGE (SIDEWALK) | (S.F./PERCENT) | 234±/0.05 | 499±/1.0 | | | |
| LOT COVERAGE (DRIVEWAY) | (S.F./PERCENT) | 1,318±/2.8 | 2,326±/4.9 | | | |


LZ.

LAYOUT PLAN
RESIDENTIAL DEVELOPMENT
1165 GREACEN POINT ROAD
MAMARONECK, NY, 10543

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

| No. | Revision | Date | Ву |
|-----|------------------------------|------------|-----|
| 1. | REVISED BUILDING FOOTPRINT | 04/11/2019 | SPG |
| 2. | UPDATED WETLAND LINES | 02/28/2020 | RC |
| 3. | UPDATED SURVEY | 05/11/2020 | RAR |
| 4. | REVISED PER VILLAGE COMMENTS | 06/08/2020 | RAR |
| 5. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR |
| 6. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR |
| 7. | RESUBMIT TO VILLAGE HCZMC | 09/02/2020 | RAR |
| | Previous Editions Obsolete | | |





SEQUENCE OF CONSTRUCTION

- CONSTRUCTION SHALL BE SEQUENCED IN SUCH A MANNER THAT ANY AREA WHICH IS DISTURBED SHALL FIRST BE PROTECTED WITH SEDIMENT EROSION CONTROLS AS INDICATED ON THIS PLAN. PARTICULAR REQUIREMENTS ARE GIVEN
- 1. DEMOLITION OF EXISTING BUILDINGS AS REQUIRED.
- 2. INSTALLATION OF SEDIMENT AND EROSION CONTROL MEASURES AS INDICATED ON THIS PLAN.
- 3. CLEAR UNDEVELOPED PORTION OF PROPERTY WHICH IS TO BE DEVELOPED. 4. STRIP AND STOCKPILE TOPSOIL.
- 5. BEGIN BUILDING AND PARKING LOT CONSTRUCTION, ROUGH GRADING.
- 6. INSTALL STORM DRAIN SYSTEM COMPLETE (IMMEDIATELY INSTALL HAYBALE FILTERS ON ALL INLETS).
- 7. INSTALL PUBLIC UTILITIES (GAS, ELECTRIC AND TELEPHONE) AS REQUIRED. 8. INSTALL CONCRETE AND ASPHALT CONCRETE PAVEMENT COMPLETE.
- 9. FINISH GRADING, REDISTRIBUTE TOPSOIL AND ESTABLISH VEGETATION AND/OR
- 10. CLEAN PAVEMENTS AND STORM DRAIN SYSTEM OF ALL ACCUMULATED SEDIMENT IN CONJUNCTION WITH THE REMOVAL OF ALL TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES.
- . COMPLETE SITE AND BUILDING CONSTRUCTION.

LEGEND

EXISTING WETLAND SETBACK

PROPOSED SILT FENCE

PROPOSED LIMIT OF DISTURBANCE PROPOSED CONSTRUCTION FENCE

PROPOSED STABILIZED CONSTRUCTION

ENTRANCE

PROPOSED STOCKPILE AREA


- THIS PLAN IS FOR TEMPORARY EROSION AND SEDIMENT CONTROL INFORMATION ONLY.
- PRIOR TO BEGINNING ANY CLEARING, GRUBBING OR EXCAVATION, ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH ALL THE PLANS AND SPECIFICATIONS. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL THE SITE IS STABILIZED. FINAL STABILIZATION OF LANDSCAPED AREAS SHALL BE IN
- 4. THE CONTRACTOR SHALL INSPECT AND MAINTAIN ON-SITE EROSION AND SEDIMENT CONTROL MEASURES ON A DAILY BASIS. ALL COLLECTED SEDIMENT WITHIN SEDIMENT BARRIERS SHALL BE REMOVED PERIODICALLY AS REQUIRED TO MAINTAIN THE FUNCTION OF THE SEDIMENT BARRIERS. ALL SEDIMENT COLLECTED SHALL BE RESPREAD ON-SITE WITHIN
- EVIDENCE OF SEDIMENTATION ON A WEEKLY BASIS, AFTER EACH RAINSTORM, AND AS MAY BE REQUIRED OR DIRECTED BY ALL APPLICABLE APPROVALS AND PERMITS. THE CONTRACTOR SHALL DOWNSTREAM AREAS TO ALL AUTHORITIES HAVING JURISDICTION AND
- 7. STOCKPILING OF CONSTRUCTION MATERIAL SHALL BE PLACED ON-SITE IN THE AREA DESIGNATED ON THIS PLAN OR AS APPROVED BY THE OWNERS REPRESENTATIVE. STOCKPILED EXCAVATED MATERIAL SHALL HAVE TWO ROWS OF SILT FENCE LOCATED AROUND ITS PERIMETER. ALL STOCKPILED MATERIAL SHALL BE MAINTAINED IN AN ORDERLY MANNER SO AS NOT TO IMPEDE ON PEDESTRIAN AND/OR VEHICULAR TRAFFIC CIRCULATION ROUTES.
- 9. ALL EXPOSED SLOPES AND GRADED/DISTURBED AREAS, THAT WILL NOT BE FURTHER DISTURBED WITHIN 14 CALENDAR DAYS (7 DAYS FOR CONSTRUCTION SITES THAT EITHER DIRECTLY DISCHARGE TO ONE OF THE 303(d) SEGMENTS LISTED IN APPENDIX E OF THE GENERAL PERMIT OR ARE LOCATED WITHIN ONE OF THE WATERSHEDS LISTED IN APPENDIX C OF THE GENERAL PERMIT), SHALL BE TEMPORARILY SEEDED WITHIN 24 HOURS OF DISTURBANCE, IN ACCORDANCE WITH THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION (NYSDEC) "EROSION AND SEDIMENT CONTROL GUIDELINES" AND THE ANSI A300 "BEST MANAGEMENT PRACTICES FOR TREE AND SHRUB PLANTING, TRANSPLANTING, MAINTENANCE AND CARE," PREPARED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE (ISA), LATEST EDITIONS, AS
- A.1. IN SPRING, SUMMER OR EARLY FALL, SEED THE AREA WITH RYEGRASS (ANNUAL OR PERENNIAL) AT 30 POUNDS PER ACRES (APPROXIMATELY 0.7 POUNDS/1000 SQUARE FEET OR USE 1 POUND/1000 SQUARE FEET).
- 'AROOSTOOK' WINTER RYE (CEREAL RYE) AT 100 POUNDS PER ACRE (2.5 POUNDS/1000 SQUARE FEET).
- MULCH FORMS A CONTINUOUS BLANKET.
- NECESSARY TO MAINTAIN VIGOROUS, DENSE VEGETATIVE COVER.

- EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.
- ACCORDANCE WITH THE LANDSCAPE PLAN.
- STABILIZED AREAS AS DIRECTED BY THE OWNERS REPRESENTATIVE.
- 5. THE CONTRACTOR SHALL INSPECT DOWNSTREAM CONDITIONS FOR IMMEDIATELY PROVIDE A WRITTEN REPORT ON FINDINGS OF SEDIMENT IN MAKE REPAIRS AS REQUIRED OR DIRECTED.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED BY THE CONTRACTOR AS REQUIRED/WARRANTED BY FIELD CONDITIONS AND AS DIRECTED BY THE OWNERS REPRESENTATIVE, JMC, AND/OR ANY AUTHORITY HAVING JURISDICTION.
- 7. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OWNERS
- 8. ALL STORMWATER MANAGEMENT PRACTICES SHALL REMAIN UNDISTURBED AND BE PROTECTED FROM HEAVY MACHINERY TRAFFIC DURING CONSTRUCTION. HOWEVER DURING CONSTRUCTION OF THE PRACTICE THE CONTRACTOR SHALL MINIMIZE AND AVOID HEAVY MACHINERY TRAFFIC TO THE MAXIMUM EXTENT PRACTICABLE. THERE SHALL BE NO STORAGE OF MATERIALS WITHIN AREAS TO BE USED FOR STORMWATER MANAGEMENT PRACTICES. THE CONTRACTOR SHALL INSTALL CONSTRUCTION FENCE AROUND THE PRACTICE TO DISCOURAGE VEHICLE TRAFFIC.
- A. SEED MIXTURE AND RATE OF APPLICATION:
- A.2. IN LATE FALL OR EARLY WINTER, SEED THE AREA WITH CERTIFIED
- B. APPLICATION SHALL BE UNIFORM BY MECHANICAL OR HYDROSEED
- C. MULCH ALL SEEDED AREAS WITH STRAW AT A RATE OF 2 TONS PER ACRE (90 POUNDS PER 1,000 SQUARE FEET) SUCH THAT THE
- 10. ALL SEEDED AREAS SHALL BE FERTILIZED, RESEEDED, AND MULCHED AS
- 11. TEMPORARY SEED MIXTURES SHALL NOT BE PLACED ON AREAS WHERE FINAL GRADE HAS BEEN ESTABLISHED AND TOPSOIL HAS BEEN PLACED UNLESS OTHERWISE DIRECTED BY THE PROJECT LANDSCAPE ARCHITECT.

WILLIAM

 \mathbf{a}

S EL



SEDIMEN PLAN DEVELOPMENT EN POINT ROAD CK, NY, 10543

S


0 \mathcal{L} Ш


SION & CONTROL SIDENTIAL 1165 GREACE MAMARONEC

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

| No. | Revision | Date | Ву |
|-----|------------------------------|------------|-----|
| 1. | REVISED BUILDING FOOTPRINT | 04/11/2019 | SPG |
| 2. | UPDATED WETLAND LINES | 02/28/2020 | RC |
| 3. | UPDATED SURVEY | 05/11/2020 | RAR |
| 4. | REVISED PER VILLAGE COMMENTS | 06/08/2020 | RAR |
| 5. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR |
| 6. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR |
| 7. | RESUBMIT TO VILLAGE HCZMC | 09/02/2020 | RAR |
| | Previous Editions Obsolete | | |

RAR Approved: JAR Scale: 1" = 20' 07/24/2018 Project No: 18100 18100-SITE SE SE.scr





WOVEN WIRE FENCE

MESH SPACING)

48" MIN. FENCE POST

- (MIN. 14 GAUGE, MAX. 6"

10' MAX. CENTER TO CENTER

PERSPECTIVE VIEW

48" MINIMUM LENGTH FENCE - POSTS DRIVEN MINIMUM 16" INTO THE GROUND

UNDISTURBED GROUND

HEIGHT OF FILTER

24" MINIMUM

- CLOTH ABOVE GROUND,


6. THE AREA CHOSEN FOR ALL TEMPORARY SOIL STOCKPILES SHALL BE DRY AND

8. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SEEDED WITHIN

24 HOURS. PERENNIAL OR ANNUAL RYEGRASS SHALL BE PLANTED DURING

SPRING, SUMMER OR EARLY FALL. WINTER RYE (CEREAL RYE) SHALL BE

7. ALL STOCKPILED SOIL SHALL NOT CONTAIN SLOPES GREATER THAN 2:1.



Stone Outlet Sediment Trap: ST-II

CREST

2'APRON

OPTION A ONE FOOT LAYER OF N.Y.S. DOT #2 STONE MAY BE PLACED ON THE UPSTREAM SIDE OF THE RIPRAP INPLACE OF THE EMBEDDED FILTER CLOTH.

CONSTRUCTION SPECIFICATIONS

1. AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED.

4. THE STONE USED IN THE DUTLET SHALL BE SMALL RIPRAP 4'-8' ALONG WITH A 1' THICKNESS OF 2' AGGREGATE PLACED ON THE UP-GRADE SIDE ON THE

5. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMEN-SIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF

6. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE

7. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT

8. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE

Page 5.51

OTHER WOODY VEGETATION AS WELL AS OVER-SIZED STONES, ROCKS, ORGANIC

MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED.

2. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS AND

AND STONE

EMBANKMENT

TOP OF

11'MAX.

REQUIRED STORAGE

CROSS SECTION A-A

3. ALL CUT AND FILL SLOPES SHALL BE 21 OR FLATTER.

EROSION AND SEDIMENT ARE CONTROLLED.

MAXIMUM DRAINAGE AREA 5 ACRES

DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

ADAPTED FROM DETAILS PROVIDED BY: USDA - NRCS, NEW YORK STATE DEPARTMENT OF TRANSPORTATION,

NEW YORK STATE SOIL & WATER CONSERVATION COMMITTEE

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION,

SMALL RIPRAP OR EMBEDDED FILTER CLOTH IN THE RIPRAP.

THE TRAP. IT SHALL BE PLACED ON SITE AND STABILIZED.

PROFILE

AS NEEDED.

New York State Standards and Specifications

For Erosion and Sediment Control

#2 STONE (OPTIONAL)

CROWN/DRIPLINE OR 1 FOOT FOR EVERY INCH OF CALIPER WHICHEVER IS GREATER. VI ST TREE PROTECTION (DRIPLINE FENCE)

POLYETHYLENE FENCING WITH 3.5" X 1.5" OPENINGS COLOR ORANGE. STEEL POSTS INSTALLED AT 8' O.C MAINTAIN EXISTING GRADE WITHIN THE TREE PROTECTION FENCE UNLESS OTHERWISE INDICATED ON THE PLANS. INSTALL ROUGH SAWN WOOD WHERE AND AS DIRECTED BY PROJECT LANDSCAPE ARCHITECT OR PROFESSIONAL ARBORIST. SEE CHART FOR WOOD SIZE BOUND WITH 9 GAUGE WIRE. 8"-12" THICK LAYER OF MULCH ON MAINTENANCE ROAD. 5" THICK LAYER INSIDE TREE PROTECTION AREA.


8.5"X11" SIGN LAMINATED IN PLASTIC SPACED

B | 2"X6' STEEL POSTS OR APPROVED EQUAL.

TREE PROTECTION FENCE: HIGH DENSITY

EVERY 50' ALONG FENCE

5" THICK LAYER OF MULCH.



TREE PROTECTION W/ ACCESS ROAD/CONSTRUCTION AREA (DRIPLINE FENCE)

1. SEE SPECIFICATIONS FOR ADDITIONAL TREE PROTECTION REQUIREMENTS.

- 2. IF THERE IS NO EXISTING IRRIGATION, SEE SPECIFICATIONS FOR WATERING
- 3. NO PRUNING SHALL BE PERFORMED EXCEPT BY APPROVED ARBORIST.
- I. NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND REMOVAL.
- 5. SEE SITE PLANS FOR IDENTIFICATIONS/LOCATIONS OF INDIVIDUAL TREES TO BE
- 6. ALL EXCAVATION WITHIN THE CROWN/DRIPLINE OF ANY TREE SHALL BE PERFORMED UNDER THE DIRECT SUPERVISION OF THE PROJECT LANDSCAPE ARCHITECT OR PROFESSIONAL ARBORIST. SPECIAL MEASURES, SUCH AS THE USE OF AN AIR SPADE MAY BE REQUIRED.
- . THE CONTRACTOR MAY PROPOSE THE USE OF ENGINEERED MATTING OR OTHER ENGINEERED PRODUCTS IN LIEU OF MULCH, WHICH SHALL BE SUBJECT TO THE REVIEW AND APPROVAL OF ALL AUTHORITIES HAVING JURISDICTION.

TREE PROTECTION

FINISHED SUBGRADE STANDARD BACKFILL GAS SERVICE LINE 4-2" DIA. COMMUNICATIONS SAND BACKFILL 2" DIA. GAS SERVICE LINI

- 1. UTILITIES TO BE INSTALLED IN ACCORDANCE WITH THE REGULATIONS AND REQUIREMENTS OF THE UTILITY COMPANY HAVING JURISDICTION.
- 2. BACKFILL FOR PIPE AND CONDUIT SHALL BE PLACED EVENLY AND CAREFULLY AROUND AND OVER THE PIPE OR CONDUIT IN SIX (6) INCH MAXIMUM LAYERS. EACH LAYER SHALL BE THOROUGHLY AND CAREFULLY COMPACTED UNTIL TWELVE (12) INCHES OF COVER EXISTS OVER THE PIPE OR CONDUIT. THE REMAINDER OF THE BACKFILL MAY THEN BE PLACED AND COMPACTED IN A MAXIMUM OF TWELVE (12) INCH LAYERS. EACH LAYER SHALL BE COMPACTED BY APPROVED MECHANICAL TAMPING MACHINES. UNLESS OTHERWISE SPECIFIED BACKFILL SHALL BE COMPACTED TO NOT LESS THAN 92% MAXIMUM MODIFIED DENSITY IN ACCORDANCE WITH ASTM DESIGNATION D-1557 IN THE MANNER HEREIN DESCRIBED. BACKFILL SHALL PROCEED UP TO THE LINES AND GRADES AS SHOWN ON THE DRAWINGS.
- 3. CONTRACTOR SHALL STAKE THE PROPOSED SERVICE LINES AND CONDUITS PRIOR TO BACKFILLING TO ENSURE

INSTALL TRACER WIRE OVER └─ 2-4" DIA. ELECTRICAL SERVICE CONDUITS APPROVED SUBGRADE-

SERVICES DO NOT MOVE WITHIN TRENCH.

RAR Approved: JAR NOT TO SCALE 07/24/2018 roject No: **18100**

8100-details C-900

CONSTRUCTION FENCE

CONSTRUCTION ENTRANCE

9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

TEMPORARY SEDIMENT TRAP STONE OUTLET (TYPE II)

1. SPACE SUPPORT FENCE POSTS AT 6 FOOT INTERVALS.

2. DRIVE SUPPORT POSTS 2 FEET INTO GROUND. 3. FIRMLY FASTEN FENCE MATERIAL IN PLACE BY WIRING TO FENCE POST WHILE MAINTAINING TENSION ACROSS

FULL HEIGHT OF FENCE. WIRING SHALL BE DONE IN A MANNER THAT WILL PREVENT SAGGING OF FENCE MATERIAL 4. PROVIDE PERIODIC INSPECTION AND MAINTENANCE OF FENCE INCLUDING REPAIRS AS NECESSARY AND REQUIRED.

5. PLASTIC FENCE SHALL BE INTERNATIONAL ORANGE COLOR, AS MANUFACTURED BY ADPI ENTERPRISES, INC. OR APPROVED EQUAL. 6. REMOVE CONSTRUCTION FENCE AS DIRECTED BY THE OWNER'S FIELD REPRESENTATIVE.

STABILIZED

November 2016

SYMBOL

→ UNDISTURBED AREA

STONE DUTLET

SEDIMENT TRAP

ST-II

UTILITY TRENCH DETAIL


 $\square \stackrel{\sim}{\sim} \Sigma$


ANY ALTERATION OF PLANS SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW


YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY


SECTION 7209, SUBSECTION 2.


 \bigcirc Z \times











- EXISTING CONDITIONS DEPICTED ON THIS PLAN HAVE BEEN TAKEN FROM SURVEY PREPARED BY SPINELLI SURVEYING, DATED 02/22/2018, LAST REVISED 04/23/2020.
- 2. PLANT SPECIES IS REPRESENTATIVE AND SUBSTITUTIONS MAY BE REQUIRED AT TIME OF PLANTING DUE TO AVAILABILITY, TIME OF YEAR, ETC.
- WETLAND PROPER MITIGATION SHOWN PER EVANS ASSOCIATES ENVIRONMENTAL CONSULTING, INC.

| | | , | PLANT SCHE | DULE | | | _ | |
|------------|-----|-----------------------|--------------------|----------------|------------|---------|--------------|--------------|
| TREES | QTY | BOTANICAL NAME | COMMON NAME | SIZE | ROOT COND. | REMARKS | PHOTO SAMPLE | |
| AR | 1 | Acer rubrum | Red Maple | 3" - 3.5" Cal. | B & B | N/A | | |
| SHRUBS | | | | • | 1 | • | | |
| IW | 12 | llex verticillata | Winterberry | 6' - 7' Ht. | Cont. | N/A | | |
| PERENNIALS | | | | | | | | |
| АТ | 39 | Asclepias tuberosa | Butterfly Milkweed | 2' - 3' Ht. | Cont. | N/A | | ETLAND AN |
| ET | 17 | Euthamia tenuifolia | Goldenrod | 3' - 6' Ht. | Cont. | N/A | | & WE |
| GRASSES | | | | | | | | 102 |
| AV | 19 | Andropogon virginicus | Broomsedge | 2' - 4' Ht. | Cont. | N/A | | SCAPIN |
| PV | 31 | Panicum virgatum | Switch Grass | 1 gal. | Cont. | N/A | | ANDS |

| ANY ALTERATION OF PLANS, |
|-----------------------------|
| SPECIFICATIONS, PLATS AND |
| REPORTS BEARING THE SEAL |
| OF A LICENSED PROFESSIONAL |
| ENGINEER OR LICENSED LAND |
| SURVEYOR IS A VIOLATION OF |
| SECTION 7209 OF THE NEW |
| YORK STATE EDUCATION LAW, |
| EXCEPT AS PROVIDED FOR BY |
| SECTION 7209, SUBSECTION 2. |

| No. | Revision | Date | Ву | Dra Sca |
|-----|----------------------------|------------|-----|------------|
| 1. | RESUBMIT TO VILLAGE HCZMC | 07/01/2020 | RAR | |
| 2. | RESPOND TO TOWN COMMENTS | 07/22/2020 | RAR | Da |
| 3. | RESUBMIT TO VILLAGE HCZMC | 08/31/2020 | RAR | Pro |
| | | | | 18 |
| | | | | Dra |
| | | | | |
| | | | | |
| | Previous Editions Obsolete | | | |

ELISABE

