Sigalow 886 Orienta Ave, New In-Ground 20 May 2021 -


ABBREVIATIONS

SYMBOLS								
DWG	DRAWING							
DIM. DN	DIMENSION DOWN	LAV	LAVATORY	RM	ROOM	W/	WITH	
DIM		IN OR "	INCH OR INCHES	REV.	REVISION	\\ //		
CONT.	CONTINUOUS	-		REQ'D	REQUIRED	V.I.F.	VERIFY IN FIE	
COL. CONC.	COLOMN	HGT	HEIGHT	KEIINF.	REINFORCE OR	VERT	VERTICAL	
CMU COL.	CONC. MASONRY UNIT(S) COLUMN	HVAC	HEATING/VENTILATING AIR CONDITIONING	RAD. REINF.	RADIATOR REINFORCE OR	VCT	VINYL COMP	
CLG	CEILING	0115		1.01		U.O.N.	UNLESS OTH	
CAB. CL.	CLOSET	GWB	GYPSUM WALLBOARD	PSI	POUNDS PER SQUARE INCH	IV	TELEVISION	
C.H.	CEILING HEIGHT CABINET	FDN	FOUNDATION	PTD PL	PAINTED PLATE	T.O.W. TV	TOP OF WAL TELEVISION	
<u></u>		FT	FOOT OR FEET	DTD		T.O.	TRIMMED OP	
BLDG	BUILDING	FTG	FOOTING	OPG	OPENING	TYP.	TYPICAL	
B/O	BOTTOM OF	FIXT.	FIXTURE	OC	ON CENTER	TEL.	TELEPHONE	
BOT.	BOTTOM	FIN	FINISH	-				
BLK BD	BLOCK BOARD	FL	FLOOR	NO OR # NSM	NUMBER NON STRUCTURAL MEMBER	ST STRUCT	STREET STRUCTURAI	
		EXIST	EXISTING	NTS	NOT TO SCALE	STL	STEEL	
@	AT	EQ.	EQUAL	NIC	NOT IN CONTRACT	S.S.	STAINLESS ST	
ARCH.	ARCHITECTURAL	ELEV	ELEVATION			STD	STANDARD	
APPROX.	APPROXIMATELY	ELEC	ELECTRIC	MO	MASONRY OPENING	S.F.	SQUARE FEET	
ALUM	ALUMINUM	DET	DETAIL	MTL	METAL	SIPI. SQ.	SQUARE	
AFF AC	ABOVE FINISH FLOOR AIR CONDITIONING	DIA DET	DIAMETER DETAIL	MECH MAX	MECHANICAL MAXIMUM	SECT. SIM.	SECTION SIMILAR	

SUPPLY REGISTER - FLOOR (MATCH FLOOR U.O.N.) LINE OF FOOTING **ELEVATION MA** STONE VENEER SHEET NO. -- A2 CONC. FOUNDATION WALL SEE PLAN FOR WALL THICKNESS SUPPLY REGISTER - WALL DWG. NO. ------INTERIOR ELEVA SUPPLY REGISTER - CEILING ADDITIONS -SHEET NO. -NEW WOOD STUD PARTITION SEE PLAN FOR STUD SIZE ALL ALL RETURN REGISTER SHEET NO. -STUDS @ 16" O.C. (U.O.N.) NEW HOUSE DETAIL OR SECT CONSTRUCTION **DWG NO.** ----3/A1 6" INDICATES DROP IN FLOOR LEVEL INTERIOR BEARING PARTITION ^{HB} ↓— ROOM FROST FREE HOSE BIB ROOM TAG MASONRY WALL W/ WIDTH — Floor -Finish ► WOOD 9'-0" _____ CEILING BLUESTONE CAP 0 3x 7 _____ DOOR SIZE HEIGHT CENTERLINE STONE SITE WALL HEIGHT Ç ——— — $\left(1\right)$ EXTERIOR DOOR TYPES BREAK MARK EXISTING WALL TO REMAIN $\widehat{(A)}$ EXTERIOR WINDOW TYPES AREA OF NO W EXISTING CONSTRUCTION ____ TO BE REMOVED 1**REVISION TAG** STRUCTURAL SYMBOLS $\langle SD \rangle$ SPRAY FOAM INSULATION SMOKE DETECTOR SIZE & SPACING SMOKE & CARBON SC FIBERGLASS BATT INSULATION FLOOR JOISTS X" X X" MONOXIDE DETECTOR X" X X" @ 16"0.C. FLOOR MEMBER _____ **RIGID INSULATION** $\langle c \rangle$ CARBON MONOXIDE DETECTOR SEE DOOR SIZE PSL POST (UP) (A $\langle H \rangle$ HEAT DETECTOR 3x70 PSL POST (DN) ($\overline{}$ $\overline{\mathbf{Z}}$ NEW DOOR <u>3 1/2" Ø x 3/8" S</u> COLUMN W/ 5/ CAP AND BASE EXISTING DOOR Ĭ 5x5x3/8" STEEL \widehat{A} \boxtimes 5/8" STEEL CAP A NEW WINDOW BEAM POCKET ____<u>_</u>_<u>|</u>____ TOP FLANGE HA NOTE: ALL FLOOR & CEILING FRAMING ME

NOTE: THIS SHEET MAY CONTAIN SYMBOLS THAT ARE NOT APPLICABLE TO THIS PROJECT.

a Ave, Ma Ground Pool,	Residence maroneck, NY 10543 Patios & Landscaping ing Department Issue	MARSELLA ARCHITECTS, PC 178 EAST BOSTON POST ROAD, MAMARONECK, NY 10543 TEL 914 630 0 800 MARSELLA-ARCHITECTS.COM SUBMISSIONS SEAL Date Description 05-20-21 Building Department Issue
	ZONE: R-20 SEC: 9 BLOCK: 48 LOT: 57	PROJECT CONTACTS
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	LOCATION MAP	General ContractorArchitectsCum Laude Group, Inc. 122 Westmoreland Avenue, White Plains, NY 10606 T (914) 946-2488 michelle@cumlaudegroup.comFrank Marsella, AlA for Marsella Architects, PC 178 E. Bost Post Road, Mamaroneck, N.Y. 10543 T 914-630-0800 frank@marsella-architects.comStorm Water EngineerOwnerFrangione Engineering, LLC 15 Snowberry Avenue, New Canaan, CT 06840 T (203) 554-9551 F (203) 966-6957 rob.frangione@frangione.netIan and Jessica Sigalow T (617) 285-3282 ian@greycroft.comLandscape DesignerRosalia Sanni Design LLC Landscape & Garden Design 45 East Putnam Avenue, Suite 105, Greenwich, CT 06830 T (203) 918-4619 rs@rosaliasanni.comDRAWING LIST
NOM HALL ROOM TAG FLOOR WOOD CEILING WOOD CEINERLINE CENTERLINE BREAK MARK AREA OF NO WORK AREA OF NO WORK STRUCTURAL SYMBOLS SIZE & SPACING X" X X" FLOOR JOISTS X" X X" FLOOR MEMBER PSL POST (UP) (ALL POSTS) PSL POST (DN) (ALL POSTS) BY PSL POST (DN) (ALL POSTS) 3 1/2" Ø x 3/8" STEEL COLUMN W/ 5/8" STEEL CAP AND BASE (TYP.) Sx5x3/8" STEEL CAP AND BASE (TYP.) Sx5x3/8" STEEL CAP AND BASE (TYP.) BEAM POCKET J. TOP FLANGE HANGER TOP FLANGE HANGER	SAFETY DETECTOR REQUIREMENTS INTERIOR HEADER SCHEDULE INSTALLAS PROSECTION REGUIREMENTS SECTION REGUIREMENTS INSTALLAS PROVIDE INTERCONNECTED SNORE DETECTORS WITH BATTERY BACKUP (INTERCONNECTION NOT REGUIRED ATTERTING ROM CUSTOR THE PUBLICADE OF NEW YORK STATE REQUIRED IN ALTERATION RADOR RAPHING ROM CUSTOR THE VIEW (INTERCONNECTION NOT RADOR RAPHING ROM CUSTOR THE VIEW (INTERCONNECTED SNORE DETECTOR AND THE ADDRES TO AT CACH LEVEL INCLUDING DETECTOR NATION REQUIRED ATTERTATION REQUIR	 A-002 PLOT PLAN & ZONING DATA A-003 EXISTING SITE AND NEIGHBOR PHOTOS A-101 TRELLIS PLANS, DETAILS, RET. WALLS AND MAPS SI STORMWATER MANAGEMENT - SITE PLAN S2 STORMWATER MANAGEMENT - DETAILS & NOTES L-6.0 PROPOSED PLANTING PLAN L-6.1 PLANTING DETAILS & SPECIFICATIONS





Main House - Right Looking Towards Rear



Location of Proposed Pool Facing South



Across Left Neighbor



Right Neighbor



Location of Proposed Pool at Rear



Location of Proposed Pool Facing East



Sample of Stacked Landscape Wall




Across Neighbor



Across Right Neighbor



Left Neighbor




SITE PHOTOS


NEIGHBORS

M	
MARS	
	TECTS C
178 EAST BOS' MAMARONE	TON POST RD ECK, NY 10543
· · · ·	0.0800 CHITECTS.COM
therein is specifically or and location noted on not be re-used and/o purpose other than thi accompanied by the Marsella Architects, P. entity or professional and/or seal this doo	e information contained reated for the person(s) the title box and may r altered for any other s project and must be seal and signature of C. No other person(s), organization shall sign cument for any other whatsoever.
SEAL AND SIGNATURE	
Constened ARCA Constened ARSE Constants Consta	ant a
NO. SUBMISSION	DATE
A Building Departm	
NO. REVISION	DATE
Sigalow R	esidence
In-Ground & Landscap	Pool, Patios
BUILDING NAME & ADDRESS 886 Orienta Mamaroneck	Ave
	48 LOT 57
Building Departme	nt Issue
Existing Site Adjacent Ne	Photos and ighbor Photos
SCALE as noted CAD FILENAME	DRAWN BY FM/DF DATE
CAD FILENAME Sig-POOL-CD1-A001	05/20/21




DRAWING NUMBER








PRINTS NOT VALID V	VITHOUT ORIGINAL SIGNATURE & SEAL	<u></u>			
	6	P			
			1		
LEGEND:		Approximate Location of County Sewer Force Main per County Mapping	uPole		
A/C AIR CON APPROX. APPROX	IDITIONER IMATE		N55°01'25"W 4		Tax Brick Chimney Now JPL Prope Deed Co
	OF CURB			N38	№48′25″E
EL. ELEVATIO EX. EXISTING LOC. LOCATIO	ON G	of Asphalt	. Aspt		Building Envelope
T.B.R. TO BE F PR. PROPOSI	REMOVED	Edge of	S Ston	Stone Masonry Retaining Wall	
TYP. TYPICAL DMH DRAIN M V.I.F. VERIFY	IANHOLE	SEWER MANHOLE RIM=23.73 INV=14.13			Contraction of the second s
		uncrete Curb			CB EX. AS
RL FD	ROOF LEADER FOOTING DRAIN	DRAIN INLET		SEWER	LOC. OF EX. 1 LINE (V.I.F.) E PROTECTED ONSTRUCTION
	STONE WALL EX. CONTOUR LINE	SEWER MANHOLE RIM=23.70 INV=14.10		D. 35' area of the second of t	
	PR. CONTOUR LINE GRE		VEN Stone C	121	
× 10.8	EX. SPOT ELEVATION PR. SPOT ELEVATION	DRAIN INLET RIM=23.20		— GAS	APPROX. LOC. OF EX. GAS & WATER SERVICE LINES (V.I.F.) - GAS G
		INV.A=21.25 B INV.B=21.30 H H B Q	ter Line others ter Line others te bi Asphal		ROX. LOC. OF EX. DTING DRAIN PER SOURCES (V.I.F.)
	TREE TREE T.B.R.	Concrete Curl	Nate Wate		535°47' 4"W
	SEDIMENT BARRIER	Approximate Location of — County Sewer Force Main per County Mapping		Stone Masonry Retaining Wall	
CF	CONSTRUCTION FENCE	-		4.32	
1	INFIL TRATION TEST		dge of Asphal		
			ш		
	DEEP TEST				
	PERCOLATION TEST				
				I	
HISTORIC SITE PLAN	FORMED BY OTHERS & LOCATION IS INFORMATION. FRANGIONE ENGINEER				
THIS TEST HOLE.	UTILITY LOCATIONS BASED ON GROUP				
POOL IN ORDER TO	THIS PLAN IS TO DEPICT A PROPOSEI OBTAIN A BUILDING PERMIT FROM T	HE VILLAGE OF MAN	IARONECK. IT		
FRANGIONE ENGINEE	NOR IS IT INTENDED TO BE USED FO RING, LLC TAKES NO RESPONSIBILITY IR THAN THAT WHICH WAS INTENDED.	IF THIS DRAWING I			
LAND SURVEYORS, 3	RMATION OBTAINED FROM SURVEY PR 394 BEDFORD ROAD, PLEASANTVILLE,	NY 10570 PREPARE	ED FOR		
JESSICA SIGALOW SI COUNTY, NEW YORK	EL ENTITLED "TOPOGRAPHY PREPAREI TUATE IN THE VILLAGE AND TOWN OF " LAST REVISED DECEMBER 24, 2020 RVEY FRANCIONE ENGINEERING LLC	F MAMARONECK, WES D. REFER TO SURVE	STCHESTER YOR'S		
FOR THE ACCURACY	RVEY. FRANGIONE ENGINEERING, LLC OF THE ORIGINAL TOPOGRAPHIC SUI				
locations of all undergrou existence of which is pre	silities and structures have been plotted from surface indication and utilities are approximate only. Additionally, there may be of sently unknown. Any party utilizing the utility information and	other underground utilities the data depicted on this survey			
shall call "DIG SAFELY I	VEW YORK" at 800-962-7962 a minimum of forty eight (48) he ation of underground utilities.	ours prior to any construction			
FRANGIONE ENGINEERING, LI 15 SNOWBERRY LANE	LC NEW CANAAN, CT 06840				



DRAINAGE NOTES:

1. ALL PR. DRAIN PIPES SHALL BE 4" SDR-35 PVC ASTM D3034 WITH MINIMUM 1% PITCH UNLESS OTHERWISE NOTED. 2. POSITIVE PITCH SHALL BE MAINTAINED AWAY FROM THE HOUSE AND POOL AT 3. EX. DRAINAGE PATTERNS SHALL BE MAINTAINED AT ALL TIMES.

4. EXISTING HOUSE TO REMAIN. 5. SOIL STOCKPILE AREAS SHOULD NOT BE PLACED OVER EX. CULTEC SYSTEM. 6. EXCAVATOR SHALL BE TRACK-MOUNTED TO AVOID CRUSHING EX. UTILITIES. 7. LIMIT OF DISTURBANCE = $30,000 \pm$ SF (0.689 ACRES±). PROPOSED INCREASE IN IMPERVIOUS AREA = $3,435\pm$ SF. 8. PRIOR TO CONSTRUCTION, SURVEYOR SHALL SET A STABLE BENCHMARK NEAR THE PROPOSED POOL. 9. SUBSURFACE STORMWATER DETENTION FACILITY AND DRAINS TO BE SET 10' MINIMUM FROM ALL PROPERTY LINES. 10. ENGINEER TO BE GIVEN MIN. 48 HOURS NOTICE PRIOR TO INSTALLATION OF PROPOSED STORM WATER DETENTION SYSTEM. 11. A STREET OPENING/DRIVEWAY PERMIT FROM THE DEPT. OF PUBLIC WORKS IS REQUIRED FOR WATER & SEWER CONNECTIONS PER TOWN ENGINEER. 12. FOR WINTER DRAWDOWN OF POOL WATER LEVEL, A PUMP TRUCK SHALL BE USED TO REMOVE THE NECESSARY AMOUNT OF WATER TO WINTERIZE THE POOL AND THE WATER SHALL BE TRANSPORTED OFF-SITE. NO WATER SHALL BE



LOCATION MAP SCALE: 1"=500'

ZONING ANALYSIS

SECTION: 9 BLOCK: 48 LOT	: 57		
886 ORIENTA AVENUE	REQUIRED	EXISTING	PROPOSED
ZONE: R-20			
LOT SIZE: 73,018 SQ. FT.			
FRONT YARD:	25'	108.07'	NO CHANGE
ONE SIDE:	20'	23.26'	NO CHANGE
SIDE ON CORNER:			
BOTH SIDE:	45'	50.14	NO CHANGE
REAR:	30'	210.33'	NO CHANGE
ACCESSORY REAR:	6'	9.53'	NO CHANGE
ACCESSORY SIDE:	20'& 25'	2.83' &	2.83' &
LOT COVERAGE BUILDING:		155.3'	47'+
TOTAL BUILDING COVERAGE:	25,556 SF	5,944 SF	7,599 SF

TABLE OF IMPERVIOUS AREAS SURFACE EXISTING PROPOSED DIFFERENCE (SF) (SF) (SF) 4,574.0 4,574.0 0.0 HOUSE BARN 1,245.0 1,245.0 0.0 DRIVEWAY 3,759.0 3,759.0 0.0 WALKS 347.0 587.0 240.0 PADS 185.0 125.0 60.0 POOL 0.0 1,655.0 1,655.0 PATIOS 574.0 2,054.0 1,480.0 10,624.0 14,059.0 3,435.0 TOTALS


NOTE "X" (CONTRACTOR COMPLIANCE):

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND AND AGREE TO COMPLY WITH THE TERMS AND CONDITIONS OF THE STORMWATER POLLUTION PREVENTION PLAN. I ALSO UNDERSTAND THAT IT IS UNLAWFUL FOR ANY PERSON TO CAUSE OR CONTRIBUTE TO A VIOLATION OF WATER QUALITY STANDARDS."

NAME	TITLE	FIRM NAME	ADDRESS	PHONE #	SIGNATURE	DATE
					TE OF NEW	X
					\$	R)
						* 5
					PROFESSIONAL ENG	
NOTE: UNAL		NS OR ADDITIONS TO ⁻	THIS MAP IS A VIOLA	TION OF		
SECTION 72	09, SUBSECTION 2, O	F THE NEW YORK EDU	CATION LAW.			

DESCRIPTION DWG o |DATE REVISIONS PROPOSED STORMWATER MANAGEMENT FRANGIONE ENGINEERING, LLC PLAN PREPARED FOR CIVIL ENGINEERING IAN & JESSICA SIGALOW STRUCTURAL ENGINEERING LAND DEVELOPMENT 15 SNOWBERRY LANE 886 ORIENTA AVENUE NEW CANAAN, CT 06840 MAMARONECK NEW YORK (203) 554-9551 (PHONE) (203) 966-6957 (FAX) DRAWING NAME OVERALL SITE PLAN ENGIN MUNICIPALIT " MAMARONECK SHEET NO 1" = 20 APRIL 20, 2021 SHEET 1 OF SEC. 9, BLOCK 48 R.M.F LOT 5 MAMARONECK, NY\SIGALOW 886 ORIENTA AVE\SIGALOW 886 ORIENTA AVE SITE 1A.DWG

> 1016 FILE No.



This project proposes the construction of a pool & patio and remodel of the existing detached garage. The site consists of 73,018 SF, all of which are upland soils. Runoff from the site ultimately discharges to Long Island Sound.

It is anticipated that construction will commence in the Spring/Summer of 2021 after all necessary land use approvals

The following are erosion control measures to be utilized on this site during the construction period: tree protection, siltation fence barriers, stone construction entrances, wood chips for mulch and soil stockpiles.

The second phase will consist of the construction of the pool, equipment and stormwater management system

have been obtained from the Village of Mamaroneck assuming weather conditions permit. It is anticipated that

Maintenance specifications for the erosion control measures are part of this narrative. Construction

Certified Erosion & Sediment Control Specialist to inspect the site weekly in accordance with the NYSDEC guidelines. Monitoring reports shall be prepared and filed with the owner, contractor,

This project uses several Low Impact Development strategies. All work will be performed >100' from wetlands. The proposed patios will connected to a subsurface infiltration system. This system will

demonstrate that runoff rates and volumes will be attenuated for the 1- through 100-Year, 24-Hour Storms.

1. The clearing limits shall be delineated in the field by the project land surveyor. Brush shall be chipped into mulch and placed outside the construction area to be used as mulch as needed. The construction

5. Construct pool and pool equipment at this time. Interior renovations/remodel of ex. garage can occur concurrently.

9. Grading associated with the remainder of the site, located outside the limits of the house & drive shall be done at this time. Once this grading has been done, all disturbed areas outside the limits of the parking facility and the building shall be covered with a minimum of 6" of topsoil, seeded and mulched.

LONG TERM MAINTENANCE SCHEDULE: Best Management Practices (BMP's) program, for post-development conditions on the project has been developed to manage both the storm water quality. The recommendations are proposed to protect the site and downgradient areas. The success of the BMP controls requires professional and regulatory input, and monitoring through the implementation of a long-term maintenance program. Refer to the Drainage Summary Report for the post-construction maintenance requirements of the stormwater management system.

PLAN OBJECTIVES AND PRINCIPLES: The objectives of the Soil Erosion and Sediment Control Plan are to manage both the runoff and the

earthwork operations by using Best Management Practices. The objectives are as follows: a. Control erosion at its source with temporary control measures, minimize the runoff from areas of disturbance, distribute stormwater through natural vegetation before being discharged into wetland systems.

b. Keep land disturbance to a minimum. The site layout has been designed to minimize any potential impacts to off-site parcels. c. Construct the project in phases to minimize the area of the site under active construction at one time.

d. Retain existing vegetation wherever feasible. Siltation fence or other barriers will be used to limit the extent of earthwork. e. Stabilize disturbed areas as soon as practical. Earth disturbance shall not occur on a given area until

active construction is to take place in this area. f. Minimize the length and steepness of slopes. g. Maintain low runoff velocities.

h. Trap sediment on site. Siltation fence barriers and driveway construction entrance will trap sediment during

the construction period. i. Establish a maintenance and repair program during the construction period. Erosion control measures will be inspected weekly during the spring months, twice a month during the summer and/or following rainfall events of greater than 0.5 inches and repaired as needed to ensure that they function properly. j. Assign responsibility for the maintenance program. The responsibility for the maintenance program will be assigned

to the contractor who shall designate one of its supervisory personnel to be the liason to the owner's representative. the owner shall retain the services of a licensed professional who shall inspect and monitor the contractor's methods and have the authority to require modifications to the Erosion and Sediment Control Plan. The town will be copied on all inspection reports prepared on behalf of the project.

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES - MAINTENANCE REQUIREMENTS: 1. Siltation fence barriers: Accumulated sediment shall be removed when it has reached a height of 25% of

the exposed sediment barrier and disposed off is an appropriate manner. 2. Construction Entrance: Stone for the pad shall be replaced as needed during the construction process to maintain the pad and prevent the tracking of soil onto the road.

CONTROL PLAN IMPLEMENTATION:

1. The contractor shall inspect the effectiveness and condition of erosion control devices during storm events, and after each rainfall event of 0.5" or more, prior to weekends and prior to forecasted large storm events. 2. The contractor shall repair or replace damaged erosion control measures immediately, and in case, more than four hours after observing such deficiencies.

3. The contractor shall be prepared to implement interm drainage controls and erosion control measures as may be necessary during the course of construction. 4. The contractor shall make available on-site all equipment, materials and labor necessary to effect emergency

erosion control measures within four hours of any impending emergency situation. 5. The contractor shall make a final inspection, and clean up any tracked sediment on the existing road. 6. The contractor shall have on call at all times, a responsible representative who, when authorized, will mobilize

the necessary personnel, materials and equipment and otherwise provide the required action when notified of any impending emergency situation.

7. The contractor shall supply a telephone number to the town engineer, planning agent so that the contractor may be contacted during the evenings and on weekends, if necessary.

8. The contractor shall maintain a minimum of 150 If of silt fence, 30 straw bales and 1 ton of modified riprap on the site for use during emergencies during the development of the project.

> GENERAL EROSION AND SEDIMENTATION CONTROL PLAN NOTES: 1. Regrading on this site shall done in such a manner as to prevent stagnant water from collecting in depresssions. 2. All erosion and sedimentation control measures will be installed prior to the start of any construction activity. 3. All erosion and sedimentation control measures shall be constructed in accordance with the submitted construction details and in compliance with the specifications and standards found in the "Guidelines for Soil Erosion and Sediment Control" as prepared by the State of New York, latest revision. 4. Siltation fence barriers will be installed at the limit of all disturbed areas. Staked straw bales, will be utilized as necessary during the construction period. All work done shall be in accordance with the details shown on the plans.

> 5. Land disturbance will be kept to a minimum. Restabilization of all disturbed areas will occur as soon as final grading in complete. Inactive disturbed areas must be stabilized within 14 days. 6. All erosion and sedimentation control measures will be maintained in an effective conditions throughout the construction period. 7. Accumulated sediment will be removed from the control structures and disposed of in a lawful and safe manner.

8. Additional control measures will be installed during the construction period if the Zoning or Wetland Enforcement Officer requires them. The design engineer shall inspect the site periodically to ensure the proper installation of erosion control measures. 9. Regular inspections of the construction site shall be made by a representative of the Town of Mamaroneck and a professional retained by the owner to assure compliance with the approved plans.

10. The responsibility for implementing the erosion and sedimentation control plan, informing all parties engaged on the construction site of the requirements and objectives of the plan, notifying the appropriate town agencies of any transfer of this responsibility and for conveying a copy of the erosion and sedimentation control plan if title to the land

is transferred is placed upon the owner of record. INDIVIDUAL RESPONSIBLE FOR IMPLEMENTING

EROSION & SEDIMENTATION CONTROL PLAN IAN OR JESSICA SIGALOW 886 ORIENTA AVENUE MAMARONECK, NEW YORK 10543

VILLAGE OF MAMARONECK STORMWATER INSPECTION SCHEDULE

To schedule inspections, the applicant shall contact the Engineering Department at 914-777-7731 at least 48 hours before any of the following:

Installation of erosion and sediment control devices (Pre-construction)

Z:\MAMARONECK, NY\SIGALOW 886 ORIENTA AVE\SIGALOW 886 ORIENTA AVE SITE.DWG

Installation of storm water management practices and drainage structures

Completion of site clearing, Completion of rough grading,

Completion of final grading,

Close of the construction season,


Completion of final landscaping, and

8. Establishment of landscaping in public areas.

9. One year post-completion maintenance (Bond Release)

ITENANCE REQUIREMENTS	POST-CONSTRUCTION DRAINAGE SYSTEM INSPECTION & MAINTENANCE CHECKLIST									
		Storm Drainag	ge Piping and Manholes/Junction Boxes:							
eriodic basis and kept in full working on runoff quantities, pollutant loading, components be inspected and serviced operations have been completed and mpleted by an individual experienced in	 Has accumulated debris been removed? Do any manholes require additional repair? (identify below) Is there any evidence of stormwater piping failure? Has a comprehensive video inspection been completed? Yes No N/A 									
/ five years the inspections must be	Notes:									
			falls/Splash Pads/Scour Holes/Level Spreaders:					EOI	NEM	×
		 Have all 	drainage outlets been cleared of debris? outlet protections been inspected/repaired? erosion issues been repaired?	Yes	No No No	N/A		AN ANG	AEL FRANK	
ccumulated sediment at the completion		Notes:						+	Ka Z	7
ual basis.	Drywells and Infiltration Systems:							121#10	5	*
hensive video inspection of storm ations shall also be completed.		 Do units 	its been cleared of debris/sediments? require additional repair? (identify below): ning times of system been verified?	Yes	No No No	N/A			SIONAL ENG	HEI
		Notes:						PROFES	CIONAL EN	
ediments at the completion of e performed.		Roof Gutters:							0101	
he outfalls as required. er year, once in the spring and once in			umulated debris been removed from gutters? gutters require additional repair? (identify below):		No I No I					
shall be identified and corrected.		Notes:								
ations shall also be completed.							LTERATIONS OR ADDITIONS OF ADDITIONS OF THE NEW			VIOLATION
ebris and sediments upon the										
rterly basis. /ed and any repairs made to the units										
r year, once in the spring and once in										
ade as required. ations shall also be completed.										
hould be repaired as required.	No DA	λTE			DE	SCRIPTION			DWG	
	REVISIONS								•	
	PROPOSED STORMWATER MANAGEMENT PLAN PREPARED FOR IAN & JESSICA SIGALOW 886 ORIENTA AVENUE MAMARONECK NEW YORK					FRANGIONE ENGINEERING, LLC CIVIL ENGINEERING STRUCTURAL ENGINEERING LAND DEVELOPMENT 15 SNOWBERRY LANE NEW CANAAN, CT 06840				
							(203) 554–9551 (PHONE) (203) 966–6957 (FAX)			
	DETAILS & NOTES SCALE AS NOTED MUNICIPALITY MAMARONECK SHEET NO DATE APRIL 20, 2021 SHEET 2 OF 2 DRAWN R.M.F. SEC. 9, BLOCK 48 LOT 57									
								A Y	- 22	/


1016 FILE No.



ч

.

)



1. <u>SURVEY</u>: Existing spot elevations and existing contours are based upon topographical survey completed by surveyor as noted, unless otherwise indicated. Rosalia Sanni Design LLC takes no responsibility for the accuracy of the

2. SITE EXAMINATION: The Contractor, before submitting a bid, is assumed to have visited the site for the purpose of observing first hand any conditions relevant to the completion of the work. No consideration will be given based on lack of knowledge of existing conditions.

3. DISCREPANCIES & CONFLICTS: All discrepancies and conflicts between drawings, specifications, field conditions, & construction layout shall be brought to the attention of the Landscape Designer. Before ordering material, Contractor shall verify all dimensions by taking measurements at the building site and shall be responsible for their correctness. Any discrepancies from the drawings/specifications shall be referred to the Landscape Designer for adjustment before

4. WORKMANSHIP: Compliance with the drawings and the specifications with regard to the materials and methods of assembly will not itself assure acceptance of the construction. Of equal importance is good workmanship, the lack of which is sufficient cause to deny acceptance of the construction.

5. <u>MATERIAL</u>: Contractor shall furnish and install all material and equipment shown & described on the plan with exceptions only as noted. Contractors also shall furnish labor and tools necessary to complete the work.

6. WARRANTEE: All Contractors must include warrantee information in the bid and contracts

7. FOREMAN: Contractor shall have at the building site, from start to finish of the construction, a responsible foreman. In addition, Contractor shall give his personal supervision to the work. Any instructions given to the foreman shall have the same importance as if given to the Contractor in person.

8. INSURANCE: The Contractor shall maintain insurance that will protect him from claims under Workman's Compensation Acts and other employee benefits from claims for damages for bodily injury, or death, and for claims for damages to property which may arise out of and during operations under this contract, whether such operations be by himself or by any subcontractors or anyone directly or indirectly employed by either one of them. The Contractor shall file with the Owner a certificate for property damage insurance in the limits of \$1,000.000.00 for each accident and \$1,000,000.00 for the aggregate of operations. The Contractor shall also obtain any additional insurance required by the

9. DUMPSTER: The Contractor shall discuss the necessity of a trash dumpster on site with the Landscape Designer. This shall be discussed prior to bid submittal

10. TEMPORARY RESTROOM FACILITY: The Contractor shall discuss the necessity and responsibility for a temporary restroom for the site workers with the Landscape Designer. This shall be discussed prior to bid submittal.

11.PERMITS & CODES: Contractor shall obtain permits for the work as required and comply with all laws,

12.UTILITIES, SERVICES, DRAINAGE SYSTEM & SEPTIC: Contractor is responsible for locating & protecting all utilities & services prior to and during construction. Call CALL-BEFORE-YOU-DIG. Utilities damaged during

13.<u>ENGINEERING DRAWINGS</u>: Contractor will be furnished with the engineer's plans for drainage, recharge systems, retaining walls and all footers requiring engineering per local codes.

14.ADVANCE NOTIFICATION: Notify the Landscape Designer at least 3 days prior to commencement of work. Develop a proposed schedule with the Landscape Designer prior to the beginning of work. Keep the Landscape Designer informed of the progress of work and report immediately any difficulties, discrepancies or problems with

15. ALTERATIONS & CHANGE ORDERS: Any changes proposed to these drawing shall be approved by Landscape Designer prior to construction and issued in writing. If necessary, the Client must sign a change-order prior to implementation, and costs may be adjusted accordingly at that time.

. Site shall be kept organized and free of trash, and equipment stored on site shall be kept orderly and off of traveled access areas. Any machinery and supplies stored on site are at the Contractors own risk, and the Owner shall not be held liable for any theft or damage.

ii. Site shall be kept clean, and walkways and driveway shall be kept neat and clean and washed upon completion of Contractors scope of work.

ii. All debris, excess excavated material and trash shall be disposed of in a legal manner offsite. iii. Each Contractor shall provide for his scope of the work against weather, rain, wind, storms frost or heat as to maintain all work and materials, apparatus and fixtures free from injury or damage. At the end of the day's work, all new work likely to be damaged shall be covered and protected. Any work damaged by failure to provide protection as required shall be removed and replaced, or repaired, at contractor's expense. The Owner shall not be liable for any damage due to Contractor not securing and protecting materials on site.

2. EXISTING TREES: Protect existing trees from damage for the duration of construction by installation of fencing. Do no store any materials or otherwise disturb the ground under the canopy of these trees. Where fill must be placed within the drip line of trees, use porous material approved by the Landscape Designer prior to construction. See tree protection

3. TRENCHING: Trenching for utilities, irrigation and lighting shall not damage tree roots. If trenching is required under the drip line of any existing tree, Contractor shall hand dig or use air spade to aviod damage. Utilites shall be laid under

1. STAKE OUT: Stake or otherwise flag all design elements in field and review all staked work with Landscape Designer before starting installation. Layout must be approved by the Landscape Designer prior to construction.

2. SCALE: Do not scale drawings unless authorized by the Landscape Designer.

a. Plant material b. Topsoil

c. Seed d. Sod

ii. Related sections include

b. Job Conditions

c. Layout d. Masonrv

e. Lighting f. Pool

B. Standards and Nomenclature

i. All operations shall meet industry standards for plant material standards of name, size and care, conforming to the following American Standard for Nursery Stock, ANSI Z60.1 American Nursery and Landscape Association,

Washington, D.C., latest edition.

Plant schedule

a. A complete plant schedule is included in the drawings, with names, quantities, sizes and other requirements. In the event of a discrepancy in the quantity on the schedule and the quantity shown in the drawings, the drawing quantity shall prevail. The Landscape Contractor is responsible for verifying the quantity count accuracy between the schedule and drawings and in the event of a discrepancy found during the bidding process, it is the Landscape Contractor's responsibility to bring the discrepancy to the attention of the Landscape Designer. If the discrepancy is discovered after a bid is accepted, the Landscape Contractor assumes the obligation to provide plant material and labor as shown on the drawings, and will not be entitled to additional compensation b. No substitutions will be accepted without the written permission of the Landscape Designer.

ii. Plant Quality and Sizing a. All plants shall be true to species and cultivar specified. Plants shall meet the standards for size and quality set forth in the American Standard for Nursery Stock.

b. All plant material shall be healthy, vigorous, well branched and densely foliated when in leaf. Plants shall be free of disease and pests. Plants shall have healthy root systems and be free of physical damage. If any of these qualifications are not met, the Landscape Designer reserves the right to refuse the plant material and require replacement with new material meeting these quality standards. The Landscape Contractor shall not be entitled to any additional compensation in the event that plant

material is found not to meet the above standards. c. Plant material rejected shall be removed from the site within 48 hours.

iii. Plant Delivery, Storage and Handling

a. Plants shall be protected from physical damage to plant structure, root ball and desiccation during transportation, delivery, and while held on site.

b. During transportation, plant material shall be protected from wind.

c. During delivery and handling, plant material shall not be dragged, thrown, or bounced off of truck, moving machinery, or when handled by hand. Trees and shrubs shall not be lifted, dragged or pulled by the trunk or branches in any manner that will damage root ball or structure. d. Plant material stockpiled on site shall be irrigated if not planted within one day of delivery. Plants shall be maintained in healthy condition if Landscape Contractor stockpiles plants on site, and cared for in a manner that prevents damage by lack of water, wind and pests. Plants shall be located out of

direct sunlight. e. Existing plant stockpile and relocations

1. Dig and move plant material as noted in the drawings and/or tagged on site by the Landscape Designer and stockpile in location noted on drawings. If there is a construction

conflict with location designated for plant storage, Landscape Contractor shall contact Landscape Designer to determine alternate location 2. Landscape Contractor shall heel in plant material that can not be immediately relocated, and provide irrigation to maintain adequate moisture for plant health.

iv. Inspection a. The Landscape Designer shall make periodic inspections of the site and plant material. The Landscape Contractor shall contact the Landscape Designer a minimum of three (3) days prior to the delivery of any plant material. If any of the conditions described for quantity, quality or handling of the plant material are not met, the Landscape Designer will instruct the Landscape Contractor to repair the deficiencies or replace the material, at no additional cost. All rejected plant material shall be removed from the site within two (2) days of rejection.

v. Installation a. General notes

> 1. Planting shall occur when soil is frost free and workable. Planting shall not occur when soil is saturated, or damage to soil structure and significant compaction may occur. 2. Landscape Contractor is responsible for locating all sub-surface utilities and irrigation systems prior to any digging. Landscape Contractor shall contact *Call Before You Dig*, and schedule for sub-surface utilities to be flagged a minimum of three (3) days prior to any excavation. Landscape Contractor is responsible for any damage to utilities resulting from negligence or failure to comply with this requirement

> 3. The Landscape Designer shall be notified a minimum of three (3) days in advance of when the Landscape Contractor is scheduling to have plant material laid out according to the design. 4. All plants shall be placed according to quantity and locations noted on drawings.

5. Landscape Designer must approve all plant placement and layouts on site prior to the

Landscape Contractor planting. If plant material is planted without Landscape Designer approval, Landscape Contractor may be required to remove plant material and replant, at no additional cost to the Owner.

6. All plant material shall be installed straight and plumb to ground when planted. Trees and shrubs shall be installed so that root flare is 1"-2" above final grade. Ensure that no plant material is planted lower than final grade.

7. Staking is not recommended as a routine practice. Exceptions include planting in windy sites, when root system is shallow, or soil is light. Staking must be approved by Landscape Designer prior to installation

8. Backfill with specified soil (see soil specifications) and water thoroughly immediately after planting. In no case shall plant be installed and not thoroughly watered the same day. Landscape Contractor is responsible for watering plant material until irrigation system is installed. If plant material fails due to insufficient watering during this time, Landscape Contractor is responsible for all replacement costs, at no cost to the Owner.

9. Labels shall be removed from all plant material immediately after installation.

10. Landscape Designer shall inspect all plants after installation, and once approved, Landscape Contractor shall install mulch (see mulch specification). 11. Irrigation shall be provided for all newly install plant material. If an Irrigation Contractor has

been contracted for the project, Landscape Contractor is responsible for coordinating to have irrigation installed. In the event that either the irrigation system cannot be installed immediately following plant installation, Landscape Contractor shall provide temporary irrigation for plant material and assume responsibility for maintaining appropriate irrigation for plants. b. Balled and Burlaped Plant Material

1. When installing in planting pit, leave burlap in place when placing in planting pit. If ball is supported by a steel frame, remove frame. If not feasible to remove whole frame, remove a minimum of 50% from the top of root ball down. Peel back and remove burlap from minimum top 50% of rootball. If burlap is non-biodegradable material, entire wrapping must be removed. Remove all twine and string.

c. Containerized Plants

1. Remove pot from plant and gently massage root and soil to loose roots at edges prior to 2. Dispose of container offsite.

vi. Initial Acceptance

a. Upon completion of planting phase, the Landscape Contractor shall request a final inspection by the Landscape Designer. The inspection can be requested once the following has been completed: 1. All plants are installed, mulched and watered. 2. Site clean-up is complete, including removal of all trash, waste, landscape debris resulting from

installation and excess excavated material is removed. b. Upon acceptance of all work, the one year plant establishment period shall begin, and all associated warrantees.

vii. Warrantee of Plant Material a. When a plant material and labor warrantee is included in the contract, Landscape Contractor shall replace plant material when 25% or more of the visible portion of the plant has died. This shall be assessed by the Landscape Designer through a visual inspection of the leaf coverage, color of leaves,

branch health, trunk and bark. b. The warrantee provided by the Landscape Contractor shall cover all labor associated with the removal and replacement of the plant material, the cost of disposal off-site and the cost of the replacement plant material.

viii. Maintenance a. Landscape Contractor shall maintain plants installed in a healthy condition for the period of time the Landscape Contractor is continuing work on site, or through the length of the warrantee period, which ever the contract requires. b. Maintenance shall include watering, fertilization and control of disease and insect pests. All

chemicals used on site must be reviewed and approved by Landscape Designer prior to application. If these requirements are not met, any plant death resulting shall be replaced under warrantee. ix. Final Acceptance

a. At the end of the maintenance period, Landscape Contractor shall contact Landscape Designer to schedule a final acceptance walk through. b. The Landscape Designer will review all plant material installed and conditions of site as specified

here and determine if final acceptance criteria have been met. c. The Landscape Designer will instruct the Landscape Contractor of any deficiencies, and which plants are not meeting the level of acceptance. If plant material is to be replaced, the Landscape Contractor

has thirty (30) days in which to comply. B. Mulch

i. All wood/organic mulch shall be Sweet Peet ™ unless otherwise noted on drawings. ii. All stone/rock mulch shall be type and size noted in drawings. It shall be free of organic and inorganic debris and trash.

C. Top Soil

i. Top soil shall be furnished by the Landscape Contractor in sufficient quantity to provide 6" of topsoil over all areas to be seeded or sodded, 6" of top soil over areas to be planted with trees, shrubs, groundcover, and 12" in all perennial planting beds. Top soil shall not be spread on frozen ground or saturated ground. If the top soil is to be spread and there is an expected delay before it can be stabilized by plantings, mulch, sod, seed or other method, the Landscape Contractor is responsible for confirming significant rain is not in the forecast. If this is not verified, Landscape Contractor is responsible for replacing any top soil lost via run-off at no cost to the Owner

ii. Top soil shall consist of natural friable surface soil without admixtures of undesirable subsoil, refuse, or foreign materials. It shall be shredded and free from roots, hard clay or stones larger than 1" in diameter. The top soil shall be suitable for the growth of trees, shrubs, perennials, grass or any other plant material specified in the drawings and shall not be sourced from agricultural fields that use any type of herbicide to control weed growth, such as corn fields.

iii. Soil shall consist of the following content (dry weight): a. Organic Material 15-25%

b. Silt 25-45%

c. Sand 35-55% iv. Landscape Contractor shall obtain soil specification sheet when purchasing, and be able to provide it upon request to Landscape Designer.

D. Seed

i. Seed mixture shall be as specified in the drawings, consistent with the sun/shade aspect of the area to be seede ii. Seed shall be applied at a rate of 8 lbs per 1,000 sq ft (350 lbs/acre)

iii. Seed shall be applied between April 1st-June 1st or September 15th-October 15th , unless otherwise directed by Landscape Designer.

iv. On seeded slopes greater than 4:1, Landscape Contractor is responsible for including erosion control over seeded areas. Landscape Contractor is responsible for calculating cost and including in proposal. Owner shall not be responsible for additional costs if this is not included. v. Landscape Contractor is responsible for coordinating with Irrigation Landscape Contractor to ensure site is

prepared sufficiently for irrigation to commence upon installation of seed. vi. Installation

a. Cultivate soil to a depth of 2" and rake to clear of any debris 1" in diameter or larger and remove any sticks, stumps or irregularities. b. Apply a 16-16-16 fertilizer at 10 lbs per 1,000 sq ft and till into soil. Use a roller to smooth surface.

c. Apply seed using a method that ensures uniform distribution of seed. If using machinery, machinery shall be free of any weeds, seeds, or plant propagules. Rake seed gently into soil, and use a roller to lightly compact soil. d. Apply weed-free, unrotted straw mulch (wheat, oat, rye or salt hay) immediately after seed is rolled

on soil. Straw mulch shall be applied at a rate of 1-2 bales per 1,000 sq. ft., and ensure that approximately 25% of soil is visible through the straw.

e. Irrigate thoroughly with a fine spray and keep soil moist until germination begins. Continue frequent irrigation until lawn established vii. Maintenance (when included in contract)

Begins immediately after seed is sown.

b. Apply a secondary fertilization 14 days after seeding occurs. c. Mow lawn when grass reaches 2" to 2-1/2" high. At no time should more than 1/3 of the height of the grass be removed when mowing.

d. Maintain seeded lawn for 60 days or through 5 mowings, whichever is longer. e. Herbicide shall not be used, unless directed to by Landscape Designer. All herbicide products to be approved by Landscape Designer, and shall be labeled for newly seeded lawns only. Herbicide to be

applied following labeling directions. viii. Acceptance

a. Landscape Contractor shall contact Landscape Designer after the maintenance period has expired for inspection of lawn

b. Lawn will be accepted when 95% coverage is achieved. Landscape Contractor is responsible for overseeding areas found to be deficient, until lawn achieves acceptance.

E. Sod i Sod shall be 90/10 Blue Grass/Fescue mixture. Variations from this require written approval of Landscape Designer. ii. Sod shall be deep green and free of weeds and pests. Sod shall be harvested

within a maximum of 24 hours prior to installation. iii. Sod shall be kept moist. iv. Landscape Contractor is responsible for coordinating and scheduling with the

Irrigation Contractor a minimum of 48 hours prior to the installation of the sod. v. Installation a. Rough grade to designed elevations all areas where sod to be applied. Scarify earth and rake to remove all stones and debris 1" or greater in

size/diameter b. Fine grade with uniform 4" depth of topsoil (1/2" maximum allowed variance) and lightly roll surface. Fine grading shall not be performed in wet or

frozen conditions c. Moisten soil to a depth of 6".

d. Lay sod perpendicular to the slope.

e. Sod shall form a solid mass with tightly fitted joints and stagger end joints. Do not overlap sod f. Adhere sod to topsoil by lightly tamping or rolling surface.

g. On slopes exceeding 4:1, sod shall be secured with sod staples.

h. All edges shall be cut with straight edges using clean, sharp tools. i. If installing sod when the temperature is above 85 degrees, ensure that

newly laid sod maintains moisture j. Water sod by hand immediately upon completion of installation. Landscape

Contractor is responsible for coordinating with the irrigation company to ensure new sod is irrigated automatically vi. Maintenance (when included in contract)

a. The maintenance period required of the Landscape Contractor shall begin immediately after installation is complete, and will continue for either a

minimum of 45 days or after three (3) mowings, whichever is greater. b. Fertilizer shall be applied 21 days after sod is installed. c. Maintain lawn to a height of between 2"-2-1/2". At no time shall the mowing of the grass leaves be greater that 1/3rd the height of the leaf.

vii. Acceptance a. The Landscape Contractor shall contact the Landscape Designer at the end of the maintenance period to schedule an inspection. Final acceptance will

occur if 95% or greater of the sod is healthy, green and weed free. Landscape Contractor will remove and replace dead sod as directed by the Landscape Designer if the minimum success rate of the sod is not met.

NOTES:

1. Surveys provided by Thomas C. Merrits Land Surveyors 11/8/16 (parcel 1) & Summit Land Surveying 12/23/17 (parcel 2). Site Engineering plan provided by Hudson Engineering 8/8/17. Architecture plans provided by Austin Patterson Disston11/3/17.

2. Rosalia Sanni Design LLC takes no responsibility for the accuracy of the information provided by the survey. If the Contractor determines inaccuracies on site, the Contractor shall alert the Landscape Designer prior to construction of any part of the design affected by the perceived inaccuracy.

B. The Contractor shall verify the location of all utilities prior o commencement of any construction activities by contacting "Call Before You Dig". The Contractor takes full esponsibility for any utilities damaged due to not verifying utility locations, and will repair any damage at the Contractors own expense.

I. The Contractor shall obtain all permits for construction activities as required by the local municipality, state and federal regulations. All permits shall be obtained prior to commencement of the work associated with the permit. The Contractor shall abide by all rules and regulations set forth by the permits required for construction activities.

5. The Contractor shall at all times keep the construction site in an orderly condition, store materials in a pre-determined location, minimize site disturbance, and emove all debris and excess material from the site.

. The Contractor shall maintain any erosion control neasures utilized on site.

No. Date & Revision

5/6/2021 Issued for Land Use Approval

Rosalia Sanni Design LLC Landscape & Garden Design

> Greenwich, Connecticut www.rosaliasanni.com

Phone: 203-918-4619 Email: rs@rosaliasanni.com

PROJECT:

SIGALOW RESIDENCE 886 ORIENTA AVENUE VILLAGE OF MAMARONECK NY, 10543

DWG. TITLE:

PLANTING DETAILS & SPECIFICATIONS

DRAWING FILE: 2021-05-05 CD RSD rs.dwg

DRAWN BY: RS

SAVE DATE: May 6, 2021

ORIGINAL ISSUE DATE: 5/6/2021

REVISION DATE:

SHEET NO.

